

Nelson, Heindel, and Noyes

- Consulting Hydrogeologists
- Engineers
- Environmental Scientists

P.O. Box 64709 Burlington, Vermont 05406-4709

802-658-0820

FAX: 802-860-1014

November 8, 1996

Mr. Michael B. Morissette
Hazardous Materials and Waste Coordinator
Vermont Agency of Transportation
133 State Street
Montpelier, Vermont 05633

Re: Vermont Agency of Transportation

Dear Mike:

Please find attached three copies of our report on the Former District #2 Maintenance Garage, Brattleboro, Vermont.

If you have any questions or comments, please do not hesitate to call.

Best regards,

Jeffrey E. Noyes
Chief Hydrogeologist

JEN/jb

Attachment

[U:\AMCBEAN\WPDOCS\MORRIS\SET.L3]

RECEIVED
NOV 12 1996
MAINTENANCE
DIVISION

VERMONT AGENCY OF TRANSPORTATION


FORMER DISTRICT #2 MAINTENANCE GARAGE BRATTLEBORO, VERMONT

November 7, 1996

NELSON, HEINDEL, AND NOYES

NH&N

Consulting Hydrogeologists, Engineers, and Environmental Scientists



Nelson, Heindel, and Noyes

- Consulting Hydrogeologists
- Engineers
- Environmental Scientists

P.O. Box 64709 Burlington, Vermont 05406-4709

802-658-0820

FAX: 802-860-1014

VERMONT AGENCY OF TRANSPORTATION


FORMER DISTRICT #2 MAINTENANCE GARAGE

Brattleboro, Vermont

Prepared by:

Nelson, Heindel, and Noyes

Prepared for:



10/15/96 10:26 AM '96


Nov 15 10 26 AM '96

November 7, 1996

VERMONT AGENCY OF TRANSPORTATION
FORMER DISTRICT #2 MAINTENANCE GARAGE
Brattelboro, Vermont

TABLE OF CONTENTS

	<u>Page</u>
1.0 INTRODUCTION	1
2.0 SITE DESCRIPTION AND BACKGROUND	2
2.1 Site Location and Physiography	2
2.2 Existing Environmental Threats	2
2.3 Site History	2
3.0 METHODS OF INVESTIGATION	3
3.1 Monitoring Well Installation	4
3.2 Soil Screening and Sampling	4
3.3 Groundwater Sampling	4
4.0 INVESTIGATION RESULTS	5
4.1 Site Stratigraphy	5
4.2 Hydrogeology	5
4.3 Contaminant Distribution	6
5.0 SENSITIVE RECEPTOR SURVEY	7
6.0 CORRECTIVE ACTION	7
7.0 CONCLUSIONS	7



Nelson, Heindel, and Noyes

- Consulting Hydrogeologists
- Engineers
- Environmental Scientists

P.O. Box 64709 Burlington, Vermont 05406-4709

802-658-0820

FAX: 802-860-1014

VERMONT AGENCY OF TRANSPORTATION

FORMER DISTRICT #2 MAINTENANCE GARAGE Brattleboro, Vermont

1.0 INTRODUCTION

In 1989 Mr. Michael Lacroix purchased the District #2 Maintenance Garage in Brattleboro, Vermont. At the time of the sale the Agency of Transportation (AOT) had cleaned up visible surface contamination, removed all unused underground storage tanks, and cleared the site of all solid waste.

In July of 1994, the Merchants Bank initiated a Phase II site assessment of this property to determine the status of soil and groundwater contamination at the site. This work was carried out under the direction of the Johnson Company (consultant). The consultant's report dated July 29, 1994 details the levels of soil and groundwater contamination found at that time. In a letter dated August 1, 1994 to Mr. George Desch, Chief Sites Management Section, Vermont Agency of Natural Resources, the Merchants Bank states that the "possibility of contamination was known to the State" prior to the sale of the property to Mr. Michael Lacroix in 1989. The Sites Management Section evaluated the consultant's report and determined that the presence of Tetrachloroethene (PCE) in monitoring well MW-11 (Appendix 1, page 1) was their primary concern. Sites Management then requested that the AOT conduct their own site investigation to further define the distribution of PCE on the site. This report summarizes the results of the AOT investigation conducted during July of 1996.

2.0 SITE DESCRIPTION AND BACKGROUND

2.1 Site Location and Physiography

The site is located in Brattleboro, Vermont, west of Route 5 and approximately 0.5 miles north of the confluence of the West and Connecticut Rivers (Appendix 1, page 2). The site is atop a steep sided terrace overlooking the West River. The soils consist of post-glacial fluvial sand deposits overlying varved lacustrine deposits (Appendix 1, page 3 and 4). The site has been filled to level the property to the west. Bedrock underlying the site consists of slate and phyllites of the Devonian Littleton Formation (Appendix 1, pages 5 and 6).

2.2 Existing Environmental Threats

Route 5 between the intersection with Route 9 north of the site and the West River bridge south of the site is dominated by retail and service oriented industry (see Local Threat Map, Appendix 1, page 7). A portion of the site was a Ford garage from the 1940's until 1960 and there have been auto dealerships located on both sides of the site as well. There is an existing gas station northeast of the site and another gas station was formerly located across from the site just east of Route 5. Currently the site is being used for an equipment rental business, a quick lube shop, a redemption center and storage for heating/refrigeration and electrical contractors. The owner of the property also uses one of the garages for boat restoration work. There is a car wash just south of the property which has been in operation for at least 25 years.

The steep bank on the west side of the property shows evidence of active dumping of petroleum products. Just west of MW-17 approximately 20 square feet of vegetation was dead at the time of drilling and a petroleum odor was evident. Another site visit in early August revealed paint films on vegetation in the vicinity of MW-19 which had not been there at the time the well was installed.

2.3 Site History

The Agency of Transportation purchased the Brattleboro Garage property in three parcels between October, 1931 and March, 1960. The first buildings purchased were those at the north end of the property and the last was building #2. When

building #2 was purchased in 1960 it had been occupied by a Ford garage/dealership since the 1940's. The Agency of Transportation used the site for routine maintenance of vehicles and storage of materials used for roadway maintenance until Mr. Michael Lacroix purchased the property in 1989.

In June of 1987 borings were completed in the vicinity of Building #3 (old salt shed) in an area of visible surface contamination. The area had been used as the site for a portable asphalt batch plant and petroleum products associated with the operation had been spilled in the area. Kerosene and fuel oil are typically used to cutback or thin the asphalt and these were the suspected pollutants. Ten borings were completed in the area ranging in depth from 5 to 15 feet. Borings located at the front doors to the salt shed were the only ones yielding any reading on a Photovac photoionization detector (PID), ranging from 2.9 to 9.9 ppm. A recommendation was made to excavate and polyencapsulate the contaminated material. This investigation is detailed in a June 19, 1987 memo to Thomas Viall, Assistant Attorney General, from Bob Morrill, Chairman Hazardous Waste Task Force for the AOT, Dept. of Motor Vehicles. A second memo dated August 5, 1987 from Frank Aldrich, District Transportation Administrator to Donald Remick, Director of Maintenance indicates 10 to 12 cubic yards of contaminated soil were removed and polyencapsulated.

At the time of the sale in 1989, the Agency pulled all underground storage tanks which were not in use. The fire department was on site at the time and no free product was noted in any of their excavations. Monitoring wells placed in the vicinity of the old tanks by the previous consultant did indicate some residual contamination at these sites.

3.0 METHODS OF INVESTIGATION

The objective of the subsurface investigation was to determine the source and extent of PCE contamination. The investigation included soil borings and monitoring well installation, sampling and laboratory characterization of groundwater and a site survey. Each activity is detailed below.

3.1 Monitoring well Installation

Seven monitoring wells were installed to determine water quality in the vicinity of MW -11, the site of PCE contamination previously reported. Monitoring wells 15 through 19 were placed using 8 inch hollow stem augers (HSA) and wells MW-20 and MW-21 were placed with a hand auger. Monitoring well MW-15 was placed upgradient at the eastern property line to determine water quality entering the property. Well MW-16 was placed upgradient of MW-11 but down gradient of building #2, a possible source of the PCE. Three wells, MW-17, 18 and 19 were placed downgradient of MW -11 to further define the contaminant plume and MW-20 and 21 were placed at the western edge of the property to determine water quality exiting the property. A groundwater contour map is included in Appendix 1, page 8. The monitoring well construction diagrams are included in Appendix 2, pages 1-5.

3.2 Soil Screening and Sampling

Split spoon samples were taken at five foot intervals during the installation of monitoring wells MW-15 through MW-19 and composite samples were taken off the auger flights for MW-20 and MW-21. The samples were placed in plastic bags, sealed and allowed to equilibrate prior to head space sampling with an H-Nu Systems, Inc., Model PI 101 photoionization detector (PID) equipped with a 10.2 eV UV lamp. The PID was calibrated each day with a 100 ppm isobutylene gas. Boring logs detailing soil parameters and the results of PID screening can be found in Appendix 2, pages 6-18.

3.3 Groundwater Sampling

Groundwater samples from all seven monitoring wells were sampled on August 1, 1996, submitted for analysis on August 2, 1996 by EPA method 8260 (VOC's) and analyzed on August 6, 1996. The results of the water testing can be found in Appendix 3 and are discussed in Section 4.3.

4.0 INVESTIGATION RESULTS

4.1 Site Stratigraphy

The soils encountered in the borings can be divided into four horizons. The uppermost layer varies in thickness from 3 to 14 feet and consists of sand with varying amounts of gravel. The material is loose to medium dense, moist and yellowish brown to light olive brown in color. It is generally poorly sorted and appears to be a mixture of native and fill materials. The next layer consists of a very dense, moist, yellowish brown to grayish orange gravel. It was encountered in every boring at depths from 3 to 14 feet and ranges in thickness from 3 to 6 feet. Below the gravel layer is a layer of sand and silt with traces of gravel. This unit is found at depths ranging from 9 to 17 feet and is 6 to 14 feet thick. The material consists of interbedded silt, sand and sand with traces of gravel. It is typically medium dense, light olive gray and varies from moist to wet. The higher moisture contents were seen in the coarsest sediments. Beginning at a depth of 19 to 23 feet, the last unit consists of varved sand and silt interbedded with thick units of well sorted, silt and sand. All borings terminate in this unit at depths of 62 to 65 feet. Layering in the varved zone ranges from 0.05 to 0.3 feet thick and is well defined by dark minerals and oxidized horizons. The thicker bedded units have only an occasional change in grain size to define the structure. The sediments as a whole are medium dense, moist to wet, and light olive gray in color.

The sequence indicates postglacial fluvial deposition over a lacustrine sequence of beach gravel and varved silt and sand. The uppermost fluvial unit has been altered by activities at the site including excavation for structures on the site as well as in filling with borrow to level other areas.

4.2 Hydrogeology

The groundwater contour map (Appendix 1, page 8) reveals a phreatic surface sloping to the west between MW-15 and MW-19. The apparent flow direction is approximately S80W with a hydraulic gradient of 0.02 ft/ft. It was not practical to include groundwater elevations from MW-20 and MW-21 in the survey due to poor access at their location.

4.3 Contaminant Distribution

During the soil boring program split spoon and composite samples were field screened with a PID. The results are included with the annotated soil boring logs in Appendix 2. Monitoring wells 17 and 19 revealed background VOC concentrations and MW-15, MW-16 and MW-18 had VOC levels slightly above background, ranging from 0.1 to 0.6 ppm. None of the samples field screened showed any abnormal discoloration or odor.

Monitoring wells MW-7, MW-11 and wells MW-15 through MW-21 were sampled for laboratory characterization of VOC's. At the time of this survey MW-2 was dry and MW-4 could not be located. Monitoring wells MW-20 and MW-21 yielded no detectable contamination. The laboratory analytical reports are presented in Appendix 3 and the results are compiled below in Table 1.

TABLE 1 GROUNDWATER ANALYTICAL RESULTS VOLATILE ORGANIC COMPOUNDS								
Parameter	MW-7 ($\mu\text{g/L}$)	MW-11 ($\mu\text{g/L}$)	MW-15 ($\mu\text{g/L}$)	MW-16 ($\mu\text{g/L}$)	MW-17 ($\mu\text{g/L}$)	MW-18 ($\mu\text{g/L}$)	MW-19 ($\mu\text{g/L}$)	Enforce. Standard ($\mu\text{g/L}$)
Chloroform	ND	ND	ND	ND	ND	ND	TBQ	
1,1 Dichloroethene	TBQ	TBQ	ND	2.1	4.3	ND	TBQ	
Tetrachloroethene	ND	8.3	ND	11.7	23.0	3.7	8.2	0.7
1,1,1 Trichloroethane	30.7	8.5	ND	26.6	45.4	5.0	7.5	
Unidentified Peaks	0	0	0	0	0	0	0	-

- 1 Not detected
- 2 Trace below quantitation limit
- 3 No standard established

Chlorinated hydrocarbons were detected in wells MW-7, MW-11 and MW-16 through MW-19. There has been several historical uses of this property which may have involved the use of solvents and judging by the surface contamination seen during and after the current drilling program the contamination may be ongoing.

Vermont Groundwater Enforcement Standards for volatile organic compounds were exceeded in MW-16 through MW-19 for tetrachloroethene (PCE).

5.0 SENSITIVE RECEPTOR SURVEY


The contamination at this site has the potential to impact both human and environmental receptors. The primary route of human exposure would be contact with water in the West River west of the site. Since the contamination is not exposed at the ground surface and PID readings were relatively low it is unlikely that inhalation would be a significant exposure risk. Therefore dermal exposure through contact with the water or ingestion of fish impacted by the pollution would be the primary routes of exposure. Since no contamination was found downgradient from the site adjacent to fringe wetlands of the West River in wells MW-20 and MW-21, the risk of human exposure is considered negligible. The West River is the primary environmental receptor and does not appear to be impacted by pollution from this site.

6.0 CORRECTIVE ACTION

Surface and groundwater near this site are not relied upon for drinking water supplies. Therefore, even though Groundwater Standards for PCE are being exceeded, we do not believe corrective action is appropriate at this time. The contamination is limited in aerial extent and does not appear to extend outside the property lines.

7.0 CONCLUSIONS

- Tetrachloroethene is present in the groundwater at this site in levels ranging from 3.7 $\mu\text{g/L}$ to 23.0 $\mu\text{g/L}$.
- The Vermont Groundwater Enforcement Standard for PCE is 0.7 $\mu\text{g/L}$.
- The source of the contamination appears to be Building #2 with the contamination spreading downgradient to the west from this point.
- Monitoring wells MW-20 and MW-21 indicate that the contamination is not impacting the West River and the associated fringe wetlands.



AOT/BRATTLEBORO GARAGE

BRATTLEBORO,

VERMONT

SITE LOCATION MAP

SCALE: 1:25000

FILE: C:\AOTBRATT\SITEMAP

DATE: OCTOBER 2, 1996

PROJECT NO. 95302

DRAWN BY: M. Luman

PROJ. MGR: A. McBean

APPROVED: J. Noyes

Nelson, Heindel, and Noyes, Inc.




- Hydrogeology • Ecology •
- Environmental Engineering •

CONSULTING SCIENTISTS AND ENGINEERS

P.O. BOX 64708 - BURLINGTON, VERMONT 05406

PREPARED BY: INFORMATION & VISUALIZATION SERVICES



SOURCES

STATE OF VERMONT "Plan of Former VT. District #2 Transportation Complex"
JOHNSON COMPANY SITE INVESTIGATIONS 7/12/94 - 7/14/94, AND
SITE WALK WITH LACROIX REGARDING PAST USES OF PROPERTY.

NOTES

- 1) ALL DIMENSIONS AND LOCATIONS ARE APPROXIMATE.
- 2) MONITORING WELL AND SOIL BORING LOCATIONS WERE DETERMINED RELATIVE TO BUILDING CORNERS BY THE JOHNSON COMPANY.
- 3) AUTOLEVEL SURVEY CONDUCTED BY THE JOHNSON COMPANY. VERTICAL ELEVATIONS BASED ON AN ARBITRARY DATUM. VERTICAL ACCURACY IS $\pm 0.3'$.

HYDRAULIC GRADIENT :
FLOW DIRECTION :

LEGEND

- UNDERGROUND STORAGE TANK FILL PIPE
- MAGNETIC ANOMOLY
- POSSIBLE UST LOCATION
- SOIL SAMPLE LOCATION
- SOIL BORING LOCATION
- PCE TETRACHLOROETHENE READINGS (ppb)
- MONITORING WELL LOCATION 7/94
- MONITORING WELL LOCATION 7/96

Nelson, Heindel, and Noyes
• Hydrogeology • Ecology •
• Environmental Engineering •
CONSULTING SCIENTISTS AND ENGINEERS
P.O. BOX 64709
BURLINGTON, VERMONT 05406-4709
Prepared By:

DATE: NOVEMBER 1, 1996
PROJECT NO. 95302
DRAWN BY: C. Hardy
PROJ. MGR: A. McBean
APPROVED: J. Noyes

BRATTLEBORO GARAGE
VERMONT
DISTRIBUTION OF PCE
SCALE: 1"=50'

Surficial Geology of Area Surrounding Agency of Transportation, Former District II Maintenance Garage Brattleboro, VT




LEGEND ON FOLLOWING PAGE

2500 0 2500 Feet



P.O. Box 64709 - Burlington, Vermont - 05406-4709 - Tel: (802) 865-0437 - Fax: (802) 860-1014 - Email: IVS@URL@AOL.COM

SURFACE GEOLOGY EXPLANATION




SOURCE NOTES:

Surface Geology was digitized and scanned, by Wagner, Heindel, and Noyes, into a PC ARC/INFO database from 1:62500 original State of Vermont surficial geology base maps (1866-1966). These base maps were created under the supervision of David P. Stewart (1966-1968), Paul MacClintock (1963-1966), William F. Cannon (1964), G. Gordon Connally (1965), Parker E. Calkin (1965), Robert E. Behring (1966), and William W. Shills (1966). Surficial data for most of the state is available, in 15 minute quads, from WHN (802) 656-0620. Generalized Bedrock Outcrops were digitized from 1:62500 state surficial geology maps as linear features, which were buffered to 25m. Data available from WHN with surficial geology coverages. Road Centerlines were generated from pre-1990 1:60000 orthophotos (or better). Road data (RDSnn) is available from the Vermont Center for Geographic Information, VCGI (802) 656-4277. Linear Surface Waters are Digital Line Graph Data, generated from 1:24,000 USGS topographic maps. This data is available from VGIS. Town Boundaries were digitized from pre-1990 1:24000 USGS topographic maps. This coverage was created by the EPA and is available through VGIS.

Legend derived from 1:250,000 Surficial Geologic Map of Vermont (1870).


REVISION HISTORY:

Original Production - January 1995



WAGNER, HEINDEL, & NOYES, INC.
CONSULTING HYDROGEOLOGISTS, ENGINEERS, AND ENVIRONMENTAL SCIENTISTS

Bedrock Geology of Area Surrounding Agency of Transportation, Former District II Maintenance Garage Brattleboro, VT



2300 0 2300 Feet

LEGEND ON FOLLOWING PAGE



P.O. Box 64709 - Burlington, Vermont - 05406-4709 - Tel: (802) 865-0437 - Fax: (802) 860-1014 - Email: IVS@URL9.AOL.COM

BEDROCK GEOLOGY LEGEND



Road Centerline
Town Boudary



No Label
Features with no label were
not attributed on the original
source maps.



Surface Water

Topographic Contours

100 Foot Intervals
500 Feet Above Sea Level
1000 Feet Above Sea Level
1500 Feet Above Sea Level
2000 Feet Above Sea Level
2500 Feet Above Sea Level
3000 Feet Above Sea Level
3500 Feet Above Sea Level
4000 Feet Above Sea Level

Faults

Thrust Fault; Upper Plate to West
Thrust Fault; Upper Plate to East
Uncertain Thrust Fault; Upper Plate to West
Uncertain Thrust Fault; Upper Plate to East
Reverse Fault; Upthrown Side to West
Reverse Fault; Upthrown Side to East
Reverse Fault; Location Uncertain
Normal Fault; Downthrown Side to West
Normal Fault; Downthrown Side to East
Normal Fault; Location Uncertain

PLUTONIC ROCKS

PERMIAN OR TRIASSIC

White Mountain Plutonic-Volcanic Series

wle
Bostonite - Many small leucophyres
and lamprophyres not shown.

wg
Biotite and hornblende granites

ws
Hornblende, biotite, quartz and augite
syenites

wd
Nepheline syenite and pulaskite

we
Hornblende-biotite diorite; gabbro

wv
Volcanic breccia, tuff, and flows

DEVONIAN

New Hampshire Plutonic Series

nhu
Bethlehem Gneiss - Two-mica
granodiorite gneiss

nhd
Undifferentiated granitic rocks
Small dikes and sills do not show.

nhd
Metadiorite - Metagabbro, metabasite and meta-
sedite, too small to show are chiefly in the
Missisquoi, Albee and Orfordville formations.

Oliverian Plutonic Series

ohu
Biotite quartz and diorite gneiss

CAMBRIAN ROCKS

Gbh
Bridgman Hill Formation
Undifferentiated dolomite, slate and conglomerate.

Cbr
Breeze formation
Cbr - phyllite with beds of dolomite, marble,
sandstone; beds of massive dolomite locally.
Cbr - quartzite green phyllite.

Ccr
Cheshire Quartzite

Ccd
Cavendish Formation
Ccr - Readsboro Member: quartz-muscovite-schist.
Ccg - Bull Hill Gneiss: quartz-plagioclase-microcline-
biotite gneiss.
Ccm - bull dolomite.

Cca
Clarendon Springs, Ticonderoga,
and Rock River Dolomites;
Gorge Formation

Cda
Dunham Dolomite

Cdb
Danby and Potsdam Formations
Interbedded quartzite and dolomite.

Cdc
Dalton Formation
Schistose quartzite, impure dolomite,
and conglomerate.

Ch
Forestdale Marble

Chm
Hazens Notch Formation
Ch - interbedded carbonaceous and
noncarbonaceous schist.
Chb - Balidore Mountain Amphibolite Member
Chm - schist.
Chg - greenstone.

Chw
The Hatch Hill and West
Castleton Formations
Hatch Hill - calcareous quartzite.
West Castleton - siliceous, carbonaceous slate.

Cm
Monkton Quartzite

Cmo
Moosalamoo Phyllite

Co
Ottawaquechee Formation
Carbonaceous phyllite or schist containing
beds of massive quartzite.

Cp
Pinnacle Formation
Co - schistose greywacke.
Cpg - Tibbet Hill Volcanic Member

Cps
Parker Slate

Cph
Pinney Hollow Formation
Cph - Pale green phyllite with abundant magnetite.
Cpg - Chester Amphibolite Member.
Cpg - greenstone and actinolite greenstone.
Cpe - carbonaceous phyllite and schist.

Csh
Rugg Brook Formation
Dolomite, conglomerate, and sandstone.

Csm
Sweetsburg Formation
Cs - carbonaceous slate.
Csh - Hungerford State Member.
Csm - Rockledge Conglomerate Member.
Csm - Skeels Corner Slate and Mill River Conglomerate
members undifferentiated.
Csa - St. Albans Slate Member.

Cst
St. Catherine formation
Csc - slate and phyllite.
Csb - Borneoan Greywacke Member.
Csc - Zion Hill Member: quartzite
and greywacke.

Ct
Tyson Formation
Schist, conglomerate at base, phyllite
and dolomite in upper portion.

Cuf
Underhill Formation
Cu - grey-green schist.
Cuf - Fairfield Pond Member: quartzite schist.
Cug - greenstone.
Cuc - carbonaceous schist and phyllite.
Cuw - White Brook Member: sandy dolomite
with crystalline limestone.
Cuf - Forestdale Member: schist, locally quartzite.
Cuj - Jay Peak Member: schist, locally quartzite.
Cub - Foot Brook Member: schist, minor
carbonaceous interbeds.
Cua - Mount Abraham Schist Member.
Cub - Detail Member: carbonaceous schist and
schistose quartzite.
Cup - Peaked Mountain Member: greenstone.

ORDOVICIAN ROCKS

Stowe Formation
OCs - phyllite and schist.
OCnc - carbonaceous schist and phyllite.
OCsg - greenstone and amphibolite.

**Pinney Hollow, Ottawaquechee, and Stowe
Formations, undifferentiated**
Quartz schist, carbonaceous schist, and
schistose quartzite.

Ammonoosuc Volcanics

Albee Formation
Quartzite interbedded with slate and phyllite.

**Bascom Formation, and undifferentiated Luke Hill,
Naylor Ledge and Hastings Creek Limestones**
Ob - interbedded dolomite, limestone or marble,
sandstone, quartzite and limestone breccia.
Obb - Brownell Mountain Phyllite Member.

**Cutting dolomite, and undifferentiated Morgan
Corner and Wallace Creek Formations**

**Chipman, Bridport, and Beldens
Formations; Providence Island Dolomite**
Ocb - Bridport Dolomite Member.
Ocb - Beldens Member: dolomite with limestone and
marble scoring.
Ocw - Weybridge Member: limestone.
Ocb - Beldens Member: limestone with spots
of dolomite.

Cumberland Head Formation
Interbedded shale and limestone.

**Glens Falls and Orwell
Limestones, undifferentiated**

Glens Falls Formation
Highly fossiliferous limestone.

Hortonville Formation
Pyritic slate and phyllite with limy beds.

Hathaway Formation
Argillite and bedded redolite chert.

**Hortonville, or Cumberland Head, and
Glens Falls Formations, undifferentiated**

Iberville Formation
Noncalcareous black shale interbedded with dolomite.

Highgate Formation
Banded limestone and calcareous slate.

Missisquoi Formation
NORTHERN VERMONT
OMcr - phyllite and schist.
OMhb - Harlow Bridge Quartzite Member.
OMco - Coburn Hill Volcanic Member: greenstone
and amphibolite, includes pillow lavas.
OMc - carbonaceous phyllite and schist.
OMu - Umberline Hill Member: quartz and slate pebble conglomerate.
OMc - carbonaceous mica schist, quartzite and micaceous quartzite.
OMB - Barnard Volcanic Member: gneiss and amphibolite.
OMw - Wheelstone Hill Member: carbonaceous phyllite and schist.
OMm - Moretown Member: quartzite and quartz-plagioclase gneiss.

SOUTHERN VERMONT
OMc - phyllite and schist.
OMb - Barnard Volcanic Member: gneiss and amphibolite.
OMw - Wheelstone Hill Member: carbonaceous phyllite and schist.
OMm - Moretown Member: quartzite and quartz-plagioclase gneiss.

STATEWIDE
OMm - Moretown Member: quartzite and quartz-plagioclase gneiss.

Mount Hamilton Formation
Hard slates, some interbedded with quartzites and chert.

**Middlebury and Chazy Limestones;
undifferentiated Youngman and
Carman Formations**
Oml - Somewhat nodular and granular limestone
with dolomite and shaly interbeds.
Omv - Valcour Member: dark gray calcarenite
succeeded by coquina limestone.
Omc - Crown Point Member: fossiliferous limestone.
Omd - Day Point Member: calcareous quartz
sandstone and calcarenite.

Morses Line Formation
Calcareous and noncalcareous slate,
locally with limestone interbeds.

**Orwell Limestone, and Isle La Motte
and Lowville Limestones**

Orfordville Formation
Oof - carbonaceous phyllite.
Oos - Sunday Mountain Volcanics: greenstone and schist.
Oop - Post Pond Volcanics: greenstone and schist.

Partridge Formation
Op - NE VT - black carbonaceous slate and phyllite
with beds of rhyolite tuff. SE VT - carbonaceous
mica schist.
Opv - volcanic: biotite gneiss and amphibolite.

Pawlet Formation
Locally carbonaceous and pyritic, micaceous slate.

**Shelburne, Whitehall, and
Strites Pond Formations**
Chiefly a white marble or limestone with gray dolomite lineations.

Stony Point Formation
Calcareous black shale grading upward
into argillaceous limestone.

SILURIAN ROCKS

Clough Formation
NE VT - conglomerate with cobbles of quartzite and schist,
quartzite and schist matrix.
SE VT - quartzite, quartz-conglomerate and mica schist.

Fitch Formation
NE VT - weathered, sandy limestone.
SE VT - granulite, impure limestone and
dolomite, and mica schist.

Shaw Mountain Formation
N VT - quartzose limestone and calcareous quartzite.
S VT - quartzite, quartz conglomerate, conglomerate schist,
amphibolite and schist.

DEVONIAN ROCKS

Northfield Formation
Quartz-schistose slate of phyllite with
siltstone and limestone interbeds.

Gile Mountain Formation
Dg - quartz-muscovite phyllite or schist.
Dgh - Hall Stream Member: feldspathic gill,
probably volcanic, schist and amphibolite.
Dga - amphibolite.
Dgn - Meetinghouse State Member.

Littleton Formation
Gray slate and phyllite with interbeds of schistose quartzite.

Waits River Formation
Dw - quartzose and micaceous crystalline limestone.
Dws - Standing Pond Volcanic Member: amphibolite and
garnet schist.
Dwc - Crow Hill Member: tough gray quartzite of St. Albans region.
Dwb - Barton River Member: interbedded limestone and phyllite
diorite.
Dwa - Agers Cliff Limestone Member.

PRECAMBRIAN ROCKS

Mount Holly Complex
pC - biotite gneiss, and in western areas chlorite.
pCeq - quartzite, micaceous quartzite, and quartz-mica schist.
pCm - calcite and dolomite marbles.

**Undifferentiated gneissic biotite granite,
quartz monzonite, and granodiorite**

Gneiss, quartzite, calc-silicate granulite

Stamford Gneiss
Granitic biotite gneiss with megacrysts of microcline.

SOURCE NOTES:

Bedrock Geology was digitized and scanned, by Wagner, Heindel, and Noyes, into a PC ARC/INFO database from 1:62500 original State of Vermont bedrock geology base maps (1956-1966). These maps were made available by Dr. Barry Doonan, Geology Department Chairperson, University of Vermont. Bedrock data for most of the state is available, in 15 minute quads, from IVS (802) 865-0437.

Road Centerlines were generated from pre-1990 1:5000 orthophotos (or better). Road data (RDSnn) is available from the Vermont Center for Geographic Information, VCGI (802) 656-4277.

Linear Surface Waters are Digital Line Graph Data, generated from 1:24,000 USGS topographic maps. This data is available from VGIS.


Town Boundaries were digitized from pre-1990 1:24000 USGS topographic maps. This coverage was created by the EPA and is available through VGIS.



INFORMATION &
VISUALIZATION
SERVICES

P.O. Box 64709 - Burlington, Vermont - 05406-4709 - Tel: (802) 865-0437 - Fax: (802) 860-1014 - Email: IVSBURL@AOL.COM

Environmental Hazards and Locations With Test Data Surrounding Agency of Transportation, Former District II Maintenance Garage, Brattleboro, VT



- STATE DESIGNATED HAZARDOUS WASTE SITE.
(Last updated 7/96, next update 10/96)
- OLD STATE DESIGNATED HAZARDOUS WASTE SITE.
(No longer on the State HWS List as of 7/96)
- UNDERGROUND STORAGE TANK
(On the 7/96 State UST List, all sites are not located)
- ◆ SITE SPECIFIC DATA AVAILABLE. (Last updated 7-15-96, next update 10-1-96)
NOT NECESSARILY INDICATIVE OF AN ENVIRONMENTAL HAZARD.
- POTENTIAL SOURCE OF GROUNDWATER POLLUTION. (1980)
(IE. LANDFILL, INDUSTRIAL WASTE, FARMING, SALT, JUNK YARD, ETC.)


NOTE
TEST DATA SITES INDICATE
INVESTIGATIONS OF AN ECOLOGICAL,
GEOLOGICAL, OR PLANNING NATURE
MOST FEATURES ACCURATE ± 150'



INFORMATION &
VISUALIZATION
SERVICES

1000 0 1000 Feet

P.O. Box 64708 - Burlington, Vermont - 05406-4708 - Tel: (802) 865-0437 - Fax: (802) 860-1014 - Email: IVSBURL@AOL.COM



SOURCES

STATE OF VERMONT "Plan of Former VT. District #2 Transportation Complex"
JOHNSON COMPANY SITE INVESTIGATIONS 7/12/94 - 7/14/94, AND
SITE WALK WITH LACROIX REGARDING PAST USES OF PROPERTY.

NOTES

- 1) ALL DIMENSIONS AND LOCATIONS ARE APPROXIMATE.
- 2) MONITORING WELL AND SOIL BORING LOCATIONS WERE DETERMINED RELATIVE TO BUILDING CORNERS BY THE JOHNSON COMPANY.
- 3) AUTOLEVEL SURVEY CONDUCTED BY THE JOHNSON COMPANY. VERTICAL ELEVATIONS BASED ON AN ARBITRARY DATUM. VERTICAL ACCURACY IS $\pm 0.3'$.

HYDRAULIC GRADIENT : 0.023 FT/FT
FLOW DIRECTION : S80W

MONITOR WELL	T.O.C.	D.T.G.W.	ELEV. G.W. (8/1/96)
MW-7	93.36	57.42	35.94
MW-11	90.03	53.78	36.25
MW-15	90.21	49.30	40.91
MW-16	90.54	53.18	37.36
MW-17	89.84	54.39	35.45
MW-18	89.62	54.75	34.87
MW-19	93.52	58.64	34.88

LEGEND

- UNDERGROUND STORAGE TANK FILL PIPE
- MAGNETIC ANOMALY
- POSSIBLE UST LOCATION
- SOIL SAMPLE LOCATION
- SOIL BORING LOCATION
- MAX PID READING FOR SOIL BORING/ MONITORING WELL LOCATION
- MONITORING WELL LOCATION 7/94
- MONITORING WELL LOCATION 7/96
- GROUNDWATER CONTOUR IN FEET

DATE: NOVEMBER 1, 1996

PROJECT NO. 95302

DRAWN BY: C. Hardy

PROJ. MGR: A. McBean

APPROVED: J. Noyes

☒ DRAFT ☐ FINAL

BRATTLEBORO GARAGE

VERMONT

BRATTLEBORO,

GROUNDWATER CONTOUR MAP

SCALE: 1"=60'

FILE: C:\BRATTLEB\SITEPLAN

Nelson, Heindel, and Noyes


• Hydrogeology • Ecology •
• Environmental Engineering •
CONSULTING SCIENTISTS AND ENGINEERS

P.O. BOX 64709
BURLINGTON, VERMONT 05406-4709

Prepared By:
Information & Visualization Services

WELL CONSTRUCTION LOG

WAGNER, HEINDEL, and NOYES, INC.
BURLINGTON, VERMONT



PROJECT AOT - BRATTLEBORO GARAGE

WELL # MW-15

JOB # 95302

TOWN/CITY/STATE BRATTLEBORO, VT

INSTALLATION DATE(S) 07-08-96

DRILLING METHOD Hollow Stem Auger

DRILLING FLUID TYPE _____ VOLUME _____

DRILLING CONTRACTOR AOT-

WELL DEVELOPED? ☒ YES ☐ NO

IF YES, THEN VOLUME RECOVERED IS 5.0 GAL

IF YES, BY WHOM? KAD/JW

DATE: 8/1/96

STATIC DEPTH TO WATER 49.30 FT. BELOW TOP OF CASING

☒ MEASURED ☐ ESTIMATED ON DATE: 8/1/96

SPLIT-SPOON SAMPLES? ☒ YES ☐ NO

IF YES, THEN INTERVAL IS 5' FT. OR ☐ CONTINUOUS

WELL PURPOSE Monitor Groundwater


REMARKS UPGRADIENT WELL

PREPARED BY A. McBEAN

DATE 08-08-96

WELL CONSTRUCTION LOG

WAGNER, HEINDEL, and NOYES, INC.
BURLINGTON, VERMONT



PROJECT AOT - BRATTLEBORO GARAGE

WELL # MW-116

JOB # 95302

TOWN/CITY/STATE BRATTLEBORO, VT

INSTALLATION DATE(S) 07-09-96

DRILLING METHOD HOLLOW STEM AUGER

DRILLING FLUID TYPE _____ VOLUME _____

DRILLING CONTRACTOR AOT

WELL DEVELOPED? ☒ YES ☐ NO

IF YES, THEN VOLUME RECOVERED IS 4.0 GAL

IF YES, BY WHOM? KAD/JW

DATE: 8/1/96

STATIC DEPTH TO WATER 53.18 FT. BELOW TOP OF CASING

☒ MEASURED ☐ ESTIMATED ON DATE: _____

SPLIT-SPOON SAMPLES? ☒ YES ☐ NO

IF YES, THEN INTERVAL IS 5.0 FT. OR ☐ CONTINUOUS

WELL PURPOSE MONITOR GROUNDWATER

REMARKS _____

PREPARED BY A. McBEAN

DATE 08-08-96

WELL CONSTRUCTION LOG

WAGNER, HEINDEL, and NOYES, INC.
BURLINGTON, VERMONT

ELEV 89.84 FT.

GROUND SURFACE

88.84 FT.

CASING JOINTS:

☐ NONE

☒ FLUSH-THREADED

☐ SOLVENT-WELDED

☐ OTHER:

TOP OF WELL SCREEN:

4.39 FT. ☒ ABOVE

☐ BELOW

WATER TABLE

TOTAL DEPTH:

60.0'

☒ LOCKING WELL GUARD, FLUSH

☒ CAP

SURFACE SEAL:

☒ CEMENT

☐ BENTONITE

☐ CUTTINGS

DRILLED HOLE DIA. = 8.0 IN.

WELL CASING DIA. 2.0 IN.

MAT'L PVC

BACKFILL:

☐ GROUT

☒ CUTTINGS

BENTONITE:

☐ SLURRY

☒ PELLETS

15'-16' bgs

43'-44' bgs

WATER LEVEL:

ELEV 35.45

WELL SCREEN:

MAT'L PVC

SLOT 0.02 IN.

LENGTH 10.0 FT.

SOCK: ☒ YES

☐ NO

☐ GRAVEL PACK

☐ SAND PACK

☒ FORMATION COLLAPSE

SUMP: ☐ YES

☒ NO

BORING DEPTH:

☒ 62 FT.

☐ _____ FT.

BELOW WATER TABLE

☐ _____ FT. INTO IMPEDING MATERIAL

☐ TO REFUSAL

☐ _____ FT. INTO BEDROCK

PROJECT AOT - BRATTLEBORO GARAGE

WELL # MW-17

JOB # 95302

TOWN/CITY/STATE BRATTLEBORO, VT

INSTALLATION DATE(S) 07-11-96

DRILLING METHOD Hollow Stem Auger

DRILLING FLUID TYPE _____ VOLUME _____

DRILLING CONTRACTOR AOT

WELL DEVELOPED? ☒ YES ☐ NO

IF YES, THEN VOLUME RECOVERED IS 3.0 AL

IF YES, BY WHOM? KAD/JW

DATE: 8/1/96

STATIC DEPTH TO WATER 54.39 FT. BELOW TOP OF CASING

☒ MEASURED ☐ ESTIMATED ON DATE: _____

SPLIT-SPOON SAMPLES? ☒ YES ☐ NO

IF YES, THEN INTERVAL IS 5.0 FT. 0

☐ CONTINUOUS

WELL PURPOSE Monitor Groundwater

REMARKS _____

PREPARED BY A. McBEAN

DATE 08-08-96

WAGNER, HEINDEL, and NOYES, INC.
BURLINGTON, VERMONT


WAGNER, HEINDEL, and NOYES, INC.
BURLINGTON, VERMONT

PROJECT AOT - BRATTLEBORO GARAGE
WELL # MW-18
JOB # 95302
TOWN/CITY/STATE BRATTLEBORO, VT
INSTALLATION DATE(S) 07-10-96
DRILLING METHOD HOLLOW STEM AUGER
DRILLING FLUID TYPE _____ VOLUME _____
DRILLING CONTRACTOR AOT
WELL DEVELOPED? ☒ YES ☐ NO
IF YES, THEN VOLUME RECOVERED IS 5.0 GAL
IF YES, BY WHOM? KAD/JW
DATE: 8/1/96
STATIC DEPTH TO WATER 54.75 FT. BELOW TOP OF CASING
☒ MEASURED ☐ ESTIMATED ON DATE: _____
SPLIT-SPOON SAMPLES? ☒ YES ☐ NO
IF YES, THEN INTERVAL IS 5.0 FT. OR
☐ CONTINUOUS
WELL PURPOSE MONITOR GROUNDWATER
REMARKS _____

PREPARED BY A. McBEAN
DATE DB-08-96

WELL CONSTRUCTION LOG

WAGNER, HEINDEL, and NOYES, INC.
BURLINGTON, VERMONT



PROJECT AOT - BRATTLEBORO GARAGE

WELL # MW-19

JOB # 95302

TOWN/CITY/STATE BRATTLEBORO, VT

INSTALLATION DATE(S) 07-10 & 11-96

DRILLING METHOD HOLLOW STEM AUGER

DRILLING FLUID TYPE _____ VOLUME _____

DRILLING CONTRACTOR AOT

WELL DEVELOPED? ☒ YES ☐ NO

IF YES, THEN VOLUME RECOVERED IS 5.0 AL

IF YES, BY WHOM? KAD/TW

DATE: 8/1/96

STATIC DEPTH TO WATER 58.67 FT. BELOW TOP OF CASING

☒ MEASURED ☐ ESTIMATED ON DATE: _____

SPLIT-SPOON SAMPLES? ☒ YES ☐ NO

IF YES, THEN INTERVAL IS 5.0' FT. ☐ CONTINUOUS

WELL PURPOSE MONITOR GROUNDWATER

REMARKS _____

PREPARED BY A. McBEAN

DATE 08-08-96

SOIL BORING LOG

NELSON, HEINDEL & NOYES P.O. BOX 64709 BURLINGTON, VT 05406-4709				Project: AOT -Brattleboro Garage		Boring Number: MW-15 Sheet 1 of 2 Project Number: 95302			
Boring Company: AOT Foreman: R. Holt NH&N Staff: Alan McBean						Boring Location: Ground Elevation: Date Started: 7/8/96 Date Ended: 7/8/96			
<u>Casing</u> Size: 8" HSA, 3" ID Hammer: Fall:				<u>Sampler</u> Type: 2.0" SS Other: Hammer: 140 lb. Fall: 30 "		Groundwater Readings Date Stabil. Time Depth Casing			
Sample				Sample Description		Strata Change & General Description		Field Testing PID	Equipment or Well Installed
No	Rec	Depth	Blows						
		0-0.1"		Pavement.					
		0.1-5.0		Moist, light olive brown, fine to medium sand.				0.0	
1	1.1'	5-7	3,5,10,13	Medium dense, moist, light olive brown, fine to medium sand with a little gravel.		Horizontally laminated with oxidized horizons		0.0	
2	1.0	10-12	24,44,48,34	Very dense, moist, dusky yellow gravel.		Gravelly to a depth of 14.0'.		0.1	
3	1.5	15-17	5,5,6,5	Medium dense, moist to wet, light olive gray; interbedded fine sand and silt with trace of gravel.				0.1	
4	1.2	20-22	3,5,9,11	Medium dense, moist to wet, light olive gray, interbedded fine and medium sand with trace of gravel.		Layers are 6-inches thick.		0.1	
5	1.7	25-27	5,6,5,7	Medium dense, moist to wet, light olive gray, varved fine sand and silt.		No gravel found below 25'.		0.1	
6	1.7'	30-32	4,6,9,12	Medium dense, moist, light olive gray, varved silt and very fine sand.				0.2	
7	1.7	35-37	4,10,11,12	Medium dense, moist, light olive gray, varved silt with some sand.		Denser horizon begins at 38.0'		0.1	
8	1.7	40-42	7,17,14,16	Dense, moist, light olive gray, varved silt.		0.5' layer of fine sand at 41.0'.		0.1	
9	1.8	45-47'	7,13,14,17	Medium dense, moist/wet, light olive gray, varved silt and sand.		Wet at 46.0'.		0.0	
10	1.2'	50-52'	9,16,18,24	Dense, wet, light olive gray, fine sand.		Change to more massive bedding (no varves). Soil density also decreases.		0.0	

NELSON, HEINDEL & NOYES P.O. BOX 64709 BURLINGTON, VT 06406-4709				Project: AOT -Brattleboro Garage	Boring Number: MW-15 Sheet 1 of 2 Project Number: 95302																																											
11	2.0'	55-57	5,9,14,16	Medium dense, wet, light olive gray silt with little sand.		0.0																																										
12	2.0'	60-62	4,9,12,17	Medium dense, wet, light olive gray sand with a 0.5' thick silt layer at 61.5'. Bottom of hole at 62.0'.		0.0																																										
<u>Proportions Used</u> Trace: 0 to 10% Little: 10 to 20% Some: 20 to 35% And: 35 to 50%		<u>Penetration Resistance</u> 140 lb wt falling 30" on 2" O.D. Sampler <table><tr><td colspan="2"><u>Cohesionless</u></td><td colspan="2"><u>Cohesive</u></td></tr><tr><td colspan="2"><u>Density</u></td><td colspan="2"><u>Consistency</u></td></tr><tr><td>0-4</td><td>Very Loose</td><td>0-2</td><td>Very Soft</td></tr><tr><td>5-9</td><td>Loose</td><td>3-4</td><td>Soft</td></tr><tr><td>10-29</td><td>Med. Dense</td><td>5-8</td><td>M/Stiff</td></tr><tr><td>30-49</td><td>Dense</td><td>9-16</td><td>Stiff</td></tr><tr><td>50+</td><td>Very Dense</td><td>16-30</td><td>Very Stiff</td></tr><tr><td></td><td></td><td>31+</td><td>Hard</td></tr></table>				<u>Cohesionless</u>		<u>Cohesive</u>		<u>Density</u>		<u>Consistency</u>		0-4	Very Loose	0-2	Very Soft	5-9	Loose	3-4	Soft	10-29	Med. Dense	5-8	M/Stiff	30-49	Dense	9-16	Stiff	50+	Very Dense	16-30	Very Stiff			31+	Hard	<u>Well Construction Legend</u> <table><tr><td>Concrete Finish and</td><td>Bentonite to 20' BGS</td></tr><tr><td></td><td>9-8' BGS</td></tr><tr><td>Grout 8-2' BGS</td><td>Silica Sand 20'-9' BGS</td></tr><tr><td>Backfill</td><td>Bedrock</td></tr></table>			Concrete Finish and	Bentonite to 20' BGS		9-8' BGS	Grout 8-2' BGS	Silica Sand 20'-9' BGS	Backfill	Bedrock
<u>Cohesionless</u>		<u>Cohesive</u>																																														
<u>Density</u>		<u>Consistency</u>																																														
0-4	Very Loose	0-2	Very Soft																																													
5-9	Loose	3-4	Soft																																													
10-29	Med. Dense	5-8	M/Stiff																																													
30-49	Dense	9-16	Stiff																																													
50+	Very Dense	16-30	Very Stiff																																													
		31+	Hard																																													
Concrete Finish and	Bentonite to 20' BGS																																															
	9-8' BGS																																															
Grout 8-2' BGS	Silica Sand 20'-9' BGS																																															
Backfill	Bedrock																																															

(U:\AMCBEAN\WPDOCS\AOT.SB1)

SOIL BORING LOG

NELSON, HEINDEL & NOYES P.O. BOX 64709 BURLINGTON, VT 05406-4709				Project: AOT - Brattleboro Garage		Boring Number: MW-16 Sheet 1 of 2 Project Number: 95302			
Boring Company: AOT Foreman: R. Holt NH&N Staff: Alan McBean						Boring Location: Ground Elevation: Date Started: 7/9/96 Date Ended: 7/9/96			
Casing Size: 8" HSA, 3" I.D. Hammer: Fall:				Sampler Type: 2.0" O.D. SS Hammer: 140 lb. Fall: 30 "		Other:		Groundwater Readings Date Stabil. Time Depth Cashin	
Sample				Sample Description		Stratra Change & General Description		Field Testing PID Equipment or Well Installed	
No	Rec	Depth	Blows						
		0.0-0.1'		Pavement.				0.0	
		0.1-3'		Moist, light olive brown sand with some gravel.				0.0	
		3'-5'		Moist, grayish orange gravel.				0.0	
1	1.3'	3-5	2,2,2,3	Very loose, dry to moist, light olive gray, sand with some silt.				0.0	
2	1.2	5-7	3,2,1,2	Very loose, moist, olive brown sand with some silt.				0.0	
3	1.3	10-12	2,3,3,2	Loose, moist, light olive gray sand and silt				0.0	
4	1.0	15-17	23,37,57,27	Very dense, moist to wet, dusky yellow gravel.		Gravel layer from 14'-17'.		0.0	
5	0.2'	20-22	18,29,34,25	Very dense, light olive brown, wet silt with some sand.		Drove stone ahead of sampler.		0.0	
6	1.3	25-27	5,10,8,9	Medium dense, wet, light olive brown varved sand and silt. Medium sand layer present every 0.4'.		Sand layers oxidized to a dusky yellow.		0.0	
7	1.6	30-32	6,9,10,19	Medium dense, light olive gray, moist, varved sand and silt.		Sand layers thicken to 0.3' from 31'-32'.		0.6	
8	1.3	35-37'	5,10,12,16	Medium dense, light olive gray, moist, varved sand and silt.				0.0	

NELSON, HEINDEL & NOYES P.O. BOX 64709 BURLINGTON, VT 05406-4709				Project: AOT - Brattleboro Garage	Boring Number: MW-16 Sheet 1 of 2 Project Number: 95302																																																																								
9	1.3'	40-42	6,10,12,22	Medium dense, light olive gray, wet/moist interbedded sand and silt.	Sand is wet, silt is moist.	0.0																																																																							
10	1.6'	45-47	9,14,14,16	Medium dense, moist, light olive gray, interbedded sand and silt (0.3' layers).		0.0																																																																							
11	1.3	50-52	11,17,19,18	Dense, moist to wet, light olive gray, varved sand and silt.	Changed from varved to massive bedding at 53.5'	0.1																																																																							
12	1.8	55-57	8,14,17,21	Dense, wet, light olive gray, well sorted fine sand, very uniform.		0.0																																																																							
13	1.8	60-62	7,11,14,19	Medium dense, wet, light olive gray, well sorted fine sand. Bottom of hole at 62.0'		0.0																																																																							
<table border="0"> <tr> <td colspan="2"><u>Proportions Used</u></td><td colspan="4"><u>Penetration Resistance</u> 140 lb wt falling 30" on 2" O.D. Sampler</td><td colspan="2"><u>Well Construction Legend</u></td></tr> <tr> <td colspan="2">Trace: 0 to 10%</td><td colspan="2"><u>Cohesionless</u></td><td colspan="2"><u>Cohesive</u></td><td>Concrete Finish and</td><td>Bentonite to 20' BGS</td></tr> <tr> <td colspan="2">Little: 10 to 20%</td><td colspan="2"><u>Density</u></td><td colspan="2"><u>Consistency</u></td><td>Grout 8-2' BGS</td><td>9-8' BGS</td></tr> <tr> <td colspan="2">Some: 20 to 35%</td><td>0-4</td><td>Very Loose</td><td>0-2</td><td>Very Soft</td><td rowspan="3">Backfill</td><td>Silica Sand 20'-9' BGS</td></tr> <tr> <td colspan="2">And: 35 to 60%</td><td>5-9</td><td>Loose</td><td>3-4</td><td>Soft</td><td></td></tr> <tr> <td colspan="2"></td><td>10-29</td><td>Med. Dense</td><td>5-8</td><td>M/Stiff</td><td></td></tr> <tr> <td colspan="2"></td><td>30-49</td><td>Dense</td><td>9-15</td><td>Stiff</td><td></td><td></td></tr> <tr> <td colspan="2"></td><td>50+</td><td>Very Dense</td><td>16-30</td><td>Very Stiff</td><td></td><td></td></tr> <tr> <td colspan="2"></td><td></td><td></td><td>31+</td><td>Hard</td><td></td><td>Bedrock</td></tr> </table>								<u>Proportions Used</u>		<u>Penetration Resistance</u> 140 lb wt falling 30" on 2" O.D. Sampler				<u>Well Construction Legend</u>		Trace: 0 to 10%		<u>Cohesionless</u>		<u>Cohesive</u>		Concrete Finish and	Bentonite to 20' BGS	Little: 10 to 20%		<u>Density</u>		<u>Consistency</u>		Grout 8-2' BGS	9-8' BGS	Some: 20 to 35%		0-4	Very Loose	0-2	Very Soft	Backfill	Silica Sand 20'-9' BGS	And: 35 to 60%		5-9	Loose	3-4	Soft				10-29	Med. Dense	5-8	M/Stiff				30-49	Dense	9-15	Stiff					50+	Very Dense	16-30	Very Stiff							31+	Hard		Bedrock
<u>Proportions Used</u>		<u>Penetration Resistance</u> 140 lb wt falling 30" on 2" O.D. Sampler				<u>Well Construction Legend</u>																																																																							
Trace: 0 to 10%		<u>Cohesionless</u>		<u>Cohesive</u>		Concrete Finish and	Bentonite to 20' BGS																																																																						
Little: 10 to 20%		<u>Density</u>		<u>Consistency</u>		Grout 8-2' BGS	9-8' BGS																																																																						
Some: 20 to 35%		0-4	Very Loose	0-2	Very Soft	Backfill	Silica Sand 20'-9' BGS																																																																						
And: 35 to 60%		5-9	Loose	3-4	Soft																																																																								
		10-29	Med. Dense	5-8	M/Stiff																																																																								
		30-49	Dense	9-15	Stiff																																																																								
		50+	Very Dense	16-30	Very Stiff																																																																								
				31+	Hard		Bedrock																																																																						

(U:\AMCBEAN\WPDOCS\AOT.SB4)

SOIL BORING LOG

NELSON, HEINDEL & NOYES P.O. BOX 64709 BURLINGTON, VT 05406-4709				Project: AOT - Brattleboro Garage		Boring Number: MW-17 Sheet 1 of 2 Project Number: 95302					
Boring Company: AOT Foreman: R. Holt NH&N Staff: Alan McBean						Boring Location: Ground Elevation: Date Started: 7/11/96 Date Ended: 7/11/96					
<u>Casing</u> Size: 8" HSA, 3" ID Hammer: Fall:						<u>Sampler</u> Type: 2.0" OD, SS Hammer: 140 lb. Fall: 30 "		Other: 		Groundwater Readings Date Depth Casing Stabil. Time	
Sample				Sample Description		Strata Change & General Description		Field Testing PID		Equipment or Well Installed	
No	Rec	Depth	Blows								
		0.0-0.1'		Pavement.				0.0			
		0.1-3'		Moist, grayish orange sand.		Gravel begins at 3.0'.		0.0			
		3'-5'		Moist, grayish orange gravel.				0.0			
1	1.3'	5-7	20,25,28,29	Very dense, moist, grayish orange gravel.		1-2" stones recovered		0.0			
2	1.5	10-12	4,6,9,10	Medium dense, moist/wet, interbedded silt/sand. Layers are 0.3' thick and horizontally laminated. Soil is olive gray.		Gravel layer ends at 9.0'.		0.0			
3	1.8	15-17	6,5,5,10	Same as 10-12 but layers are 0.7' thick.				0.0			
4	1.7	20-22	5,8,7,8	Medium dense, moist, light olive gray, varved sand and silt with some sand.		Well sorted below 23.5'.		0.0			
5	1.6	25-27	6,8,9,12	Medium dense, moist, light olive gray sand, well sorted fine sand.				0.0			
6	1.6	30-32	8,10,11,14	Same as 25'-27'.				0.0			
7	1.4	35-37	5,8,11,13	Medium dense, moist to wet, light olive gray, varved fine sand and sand with some silt.				0.0			
8	1.6	40-42'	7,12,12,14	Medium dense, moist, light olive gray sand with some silt, very uniform (no layering)				0.0			

NELSON, HEINDEL & NOYES P.O. BOX 64709 BURLINGTON, VT 05406-4709				Project: AOT - Brattleboro Garage	Boring Number: MW-17 Sheet 1 of 2 Project Number: 95302																																						
9	1.4'	45-47	7,13,14,137	Same as 40'-42'.		0.0																																					
10	1.3'	50-52	7,12,12,14	Same as 45'-47', but moist to wet.		0.0																																					
11	1.4	55-57	5,10,15,17	Medium dense, wet, light olive gray sand with laminations highlighted by dark minerals.		0.0																																					
12	2.0	60-62	4,8,12,13	Medium dense, wet, light olive gray, uniform sand. Bottom of hole at 62.0'.		0.0																																					
<u>Proportions Used</u> Trace: 0 to 10% Little: 10 to 20% Some: 20 to 35% And: 35 to 50%		<u>Penetration Resistance</u> 140 lb wt falling 30" on 2" O.D. Sampler <table><tr><td colspan="2"><u>Cohesionless Density</u></td><td colspan="2"><u>Cohesive Consistency</u></td></tr><tr><td>0-4</td><td>Very Loose</td><td>0-2</td><td>Very Soft</td></tr><tr><td>5-9</td><td>Loose</td><td>3-4</td><td>Soft</td></tr><tr><td>10-29</td><td>Med. Dense</td><td>5-8</td><td>M/Stiff</td></tr><tr><td>30-49</td><td>Dense</td><td>9-15</td><td>Stiff</td></tr><tr><td>50+</td><td>Very Dense</td><td>16-30</td><td>Very Stiff</td></tr><tr><td></td><td></td><td>31+</td><td>Hard</td></tr></table>			<u>Cohesionless Density</u>		<u>Cohesive Consistency</u>		0-4	Very Loose	0-2	Very Soft	5-9	Loose	3-4	Soft	10-29	Med. Dense	5-8	M/Stiff	30-49	Dense	9-15	Stiff	50+	Very Dense	16-30	Very Stiff			31+	Hard	<u>Well Construction Legend</u> <table><tr><td>Concrete Finish and</td><td>Bentonite to 20' BGS</td></tr><tr><td>Grout 8-2' BGS</td><td>9-8' BGS</td></tr><tr><td>Backfill</td><td>Silica Sand 20'-9' BGS</td></tr><tr><td></td><td>Bedrock</td></tr></table>			Concrete Finish and	Bentonite to 20' BGS	Grout 8-2' BGS	9-8' BGS	Backfill	Silica Sand 20'-9' BGS		Bedrock
<u>Cohesionless Density</u>		<u>Cohesive Consistency</u>																																									
0-4	Very Loose	0-2	Very Soft																																								
5-9	Loose	3-4	Soft																																								
10-29	Med. Dense	5-8	M/Stiff																																								
30-49	Dense	9-15	Stiff																																								
50+	Very Dense	16-30	Very Stiff																																								
		31+	Hard																																								
Concrete Finish and	Bentonite to 20' BGS																																										
Grout 8-2' BGS	9-8' BGS																																										
Backfill	Silica Sand 20'-9' BGS																																										
	Bedrock																																										

(U:\AMCBEAN\WPDOCS\AOT.SB3)

SOIL BORING LOG

NELSON, HEINDEL & NOYES P.O. BOX 64709 BURLINGTON, VT 05406-4709				Project: AOT - Brattleboro Garage		Boring Number: MW-18 Sheet 1 of 2 Project Number: 95302			
Boring Company: AOT Foreman: R. Holt NH&N Staff: Alan McBean						Boring Location: Ground Elevation: Date Started: 7/10/96 Date Ended: 7/10/96			
Casing Size: 8" HSA, 3" I.D. Hammer: Fall:				Sampler Type: 2.0" O.D, SS Hammer: 140 lb. Fall: 30 "		Other:		Groundwater Readings Date Stabil. Time Depth Cashin	
Sample				Sample Description		Stratra Change & General Description		Field Testing PID Equipment or Well Installed	
No	Rec	Depth	Blows						
		0.0-0.1'		Pavement.				0.0	
		0.1-3'		Moist, yellowish brown sand with some gravel.				0.0	
1	0.6'	3'-5'	4,6,7,6	Medim dense, moist, medium yellowish brown sand with little silt.		Gravel layer begins at 5.0'.		0.2	
2	0.0'	5-7		Pushed stone ahead of sampler.					
3	1.0	7-9	18,21,17,23	Dense, moist, dark yellowish brown gravel with some sand.				0.2	
4	1.5	10-12	13,7,6,5	Same as 7-9 to a depth of 10.4'. Below this is medium dense, moist, mod. olive brown silt with some sand. Uniform texture.		End gravel at 10.4'.		0.2	
6	0.0	15-17		Pushed stone ahead of sampler.					
6	1.6'	17-19	4,5,6,6	Medium dense, moist, mod. olive brown silt with some sand. Uniform layering.				0.0	
7	1.5	20-22	4,7,8,8	Medium dense, moist to wet, mod. olive brown silt and sand. Varved layer deposition highlighted by organic rich horizons.				0.0	
8	1.5	25-27	5,7,14,11	Medium dense, moist, mod. olive brown layered sand and silt. Coarser grained layers contain more moisture.				0.2	
9	1.6	30-32'	7,11,12,16	Medium dense, moist, light olive gray, uniform sand.				0.2	

NELSON, HEINDEL & NOYES P.O. BOX 64709 BURLINGTON, VT 05406-4709				Project: AOT - Brattleboro Garage	Boring Number: MW-18 Sheet 1 of 2 Project Number: 95302																													
10	1.7'	36-37	9,12,15,24	Same as 30-32 to a depth of 36'. Below this is varved, medium olive brown silt and light olive brown sand.	Cycles are 0.2' thick.	0.0																												
11	1.5'	40-42	12,17,16,18	Dense, moist, light olive gray, varved sand and silt.	Cycles highlighted by oxidized laminations.	0.0																												
12	1.7	45-47	9,14,13,15	Medium dense, moist, light olive gray, uniform sand.		0.0																												
13	1.4	50-52	9,14,15,16	Medium dense, moist, light olive gray, laminated sand with thin silt horizons.		0.0																												
14	1.8	55-57	4,8,7,13	Medium dense, wet, grayish olive sand with 0.1' thick horizons of silt.		0.0																												
15	1.8	60-62	6,8,11,14	Medium dense, wet, grayish olive sand with horizons of varved sand and silt. Bottom of hole at 65.0'.		0.0																												
<u>Proportions Used</u> Trace: 0 to 10% Little: 10 to 20% Some: 20 to 35% And: 35 to 50%		<u>Penetration Resistance</u> 140 lb wt falling 30" on 2" O.D. Sampler <table><tr><td><u>Cohesionless</u> <u>Density</u></td><td></td><td><u>Cohesive</u> <u>Consistency</u></td></tr><tr><td>0-4</td><td>Very Loose</td><td>0-2</td><td>Very Soft</td></tr><tr><td>5-9</td><td>Loose</td><td>3-4</td><td>Soft</td></tr><tr><td>10-29</td><td>Med. Dense</td><td>5-8</td><td>M/Stiff</td></tr><tr><td>30-49</td><td>Dense</td><td>9-15</td><td>Stiff</td></tr><tr><td>50+</td><td>Very Dense</td><td>16-30</td><td>Very Stiff</td></tr><tr><td></td><td></td><td>31+</td><td>Hard</td></tr></table>			<u>Cohesionless</u> <u>Density</u>		<u>Cohesive</u> <u>Consistency</u>	0-4	Very Loose	0-2	Very Soft	5-9	Loose	3-4	Soft	10-29	Med. Dense	5-8	M/Stiff	30-49	Dense	9-15	Stiff	50+	Very Dense	16-30	Very Stiff			31+	Hard	<u>Well Construction Legend</u> Concrete Finish and Bentonite to 20' BGS 9-8' BGS Grout 8-2' BGS Silica Sand 20'-9' BGS Backfill Bedrock		
<u>Cohesionless</u> <u>Density</u>		<u>Cohesive</u> <u>Consistency</u>																																
0-4	Very Loose	0-2	Very Soft																															
5-9	Loose	3-4	Soft																															
10-29	Med. Dense	5-8	M/Stiff																															
30-49	Dense	9-15	Stiff																															
50+	Very Dense	16-30	Very Stiff																															
		31+	Hard																															


(U:\AMCBEAN\WPDOCS\AOT.SBS)

SOIL BORING LOG

NELSON, HEINDEL & NOYES P.O. BOX 64709 BURLINGTON, VT 05406-4709				Project: AOT - Brattleboro Garage		Boring Number: MW-19 Sheet 1 of 2 Project Number: 95302					
Boring Company: AOT Foreman: R. Holt NH&N Staff: Alan McBean						Boring Location: Ground Elevation: Date Started: 7/10/96 Date Ended: 7/10/96					
<u>Casing</u> Size: 8" HSA, 3" ID Hammer: Fall:				<u>Sampler</u> Type: 2.0" OD, SS Hammer: 140 lb. Fall: 30 "		<u>Groundwater Readings</u> Date Time Depth Casing Stabil.					
Sample				Sample Description		Strata Change & General Description		Field Testing PID		Equipment or Well Installed	
No	Rec	Depth	Blows								
		0-2		Moist, yellowish brown, sandy loam				0.0			
1	1.7'	2-4	2,3,3,4	Loose, moist, light olive brown, uniform sand.		0.1' gravel layer at 3.6'.		0.0			
2	1.3	5-7	5,15,15,17	Same as 2-4 to 5.5'; then dense, moist, dusky yellow sand and gravel.		Gravel begins at 5.5 and ends at 9.0.		0.0			
3	1.5	10-12	4,7,7,7	Medium dense, moist, dusky yellow sand and silt.				0.0			
4	1.7	15-17	5,7,8,10	Medium dense, moist, light olive gray silt with some sand, very uniform.				0.0			
5	1.3	20-22	4,7,9,11	Medium dense, moist/wet, silt with some sand interbedded with sand horizons. Sand is saturated.							
6	1.3	25-27	4,6,9,11	Medium dense, moist to wet, light olive gray, varved sand and silt.				0.0			
7	1.7	30-32	7,9,11,10	Medium dense, moist, light olive gray sand with 0.1' silt laminations every 1.0' of recovery.				0.0			
8	1.7	35-37	5,11,11,12	Medium dense, moist, light olive gray, uniform sand.				0.0			
9	1.8	40-42	7,12,14,13	Same as 35-37'; but sample has some silt.				0.0			
10	1.6	45-47'	8,12,17,17	Same as 40-42.				0.0			

NELSON, HEINDEL & NOYES P.O. BOX 64709 BURLINGTON, VT 05406-4709				Project: AOT - Brattleboro Garage	Boring Number: MW-19 Sheet 1 of 2 Project Number: 95302																																																																						
11	1.6'	50-52	10,15,16,17	Same as 45-47 but thinly laminated and dense.		0.0																																																																					
12	1.5'	55-57	6,12,11,15	Same as 50-52; but wet and medium dense.		0.0																																																																					
13	1.8	60-62	3,6,10,11	Same as 55-57. Bottom of hole at 62.0'.																																																																							
<table> <tr> <td rowspan="5"> Proportions Used Trace: 0 to 10% Little: 10 to 20% Some: 20 to 35% And: 35 to 50% </td><td colspan="4"> Penetration Resistance 140 lb wt falling 20" on 2" O.D. Sampler </td><td colspan="3"> Well Construction Legend </td></tr> <tr> <td colspan="2">Cohesionless</td><td colspan="2">Cohesive</td><td colspan="3"></td></tr> <tr> <td colspan="2">Density</td><td colspan="2">Consistency</td><td colspan="3"></td></tr> <tr> <td>0-4</td><td>Very Loose</td><td>0-2</td><td>Very Soft</td><td colspan="3"></td></tr> <tr> <td>5-9</td><td>Loose</td><td>3-4</td><td>Soft</td><td colspan="3"></td></tr> <tr> <td></td><td>10-29</td><td>Med. Dense</td><td>5-8</td><td>M/Stiff</td><td colspan="3"></td></tr> <tr> <td></td><td>30-49</td><td>Dense</td><td>9-15</td><td>Stiff</td><td colspan="3"></td></tr> <tr> <td></td><td>50+</td><td>Very Dense</td><td>16-30</td><td>Very Stiff</td><td colspan="3"></td></tr> <tr> <td></td><td></td><td></td><td>31+</td><td>Hard</td><td colspan="3"></td></tr> </table>								Proportions Used Trace: 0 to 10% Little: 10 to 20% Some: 20 to 35% And: 35 to 50%	Penetration Resistance 140 lb wt falling 20" on 2" O.D. Sampler				Well Construction Legend			Cohesionless		Cohesive					Density		Consistency					0-4	Very Loose	0-2	Very Soft				5-9	Loose	3-4	Soft					10-29	Med. Dense	5-8	M/Stiff					30-49	Dense	9-15	Stiff					50+	Very Dense	16-30	Very Stiff							31+	Hard			
Proportions Used Trace: 0 to 10% Little: 10 to 20% Some: 20 to 35% And: 35 to 50%	Penetration Resistance 140 lb wt falling 20" on 2" O.D. Sampler				Well Construction Legend																																																																						
	Cohesionless		Cohesive																																																																								
	Density		Consistency																																																																								
	0-4	Very Loose	0-2	Very Soft																																																																							
	5-9	Loose	3-4	Soft																																																																							
	10-29	Med. Dense	5-8	M/Stiff																																																																							
	30-49	Dense	9-15	Stiff																																																																							
	50+	Very Dense	16-30	Very Stiff																																																																							
			31+	Hard																																																																							
					Concrete Finish and																																																																						
					Bentonite to 20' BGS																																																																						
					9-8' BGS																																																																						
					Grout 8-2' BGS																																																																						
					Silica Sand 20'-9' BGS																																																																						
					Backfill																																																																						
					Bedrock																																																																						

(U:\AMCBEAN\WPDOCS\AOT.SB2)



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REPORT OF LABORATORY ANALYSIS

CLIENT: Nelson, Heindel, and Noyes, Inc.
PROJECT NAME: AOT/Brattleboro Garage
REPORT DATE: August 6, 1996
DATE SAMPLED: August 1, 1996

PROJECT CODE: HNAO1621
REF. #: 92,071 - 92,080

Enclosed please find the results of the analyses performed for the samples referenced on the attached chain of custody.

Chain of custody indicated sample preservation with Sodium Azide.

All samples were prepared and analyzed by requirements outlined in the referenced method and within the specified holding times.

All instrumentation was calibrated with the appropriate frequency and verified by the requirements outlined in the referenced method.

Blank contamination was not observed at levels affecting the analytical results.

Analytical method precision and accuracy was monitored by laboratory control standards which included matrix spike, duplicate and quality control analyses. These standards were determined to be within established laboratory method acceptance limits.

Individual sample performance was monitored by the addition of surrogate analytes to each sample. All surrogate recovery data was determined to be within Laboratory QA/QC guidelines unless otherwise noted.

Reviewed by,

Harry B. Locker, Ph.D.
Laboratory Director

enclosures

LABORATORY REPORTEPA METHOD 8260 WATER MATRIXCLIENT: Nelson, Heindel, and Noyes, Inc.
PROJECT NAME: AOT/Brattleboro Garage
REPORT DATE: August 6, 1996
DATE SAMPLED: August 1, 1996
DATE RECEIVED: August 2, 1996
ANALYSIS DATE: August 5, 1996PROJECT CODE: HNAO1621
REF.#: 92,071
STATION: MW-7
TIME SAMPLED: 3:50
SAMPLER: K.A.D./J.W.

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Benzene	2	ND ¹
Bromobenzene	2	ND
Bromochloromethane	2	ND
Bromodichloromethane	2	ND
Bromoform	2	ND
Bromomethane	5	ND
n-Butylbenzene	2	ND
sec-Butylbenzene	2	ND
Carbon Tetrachloride	2	ND
Chlorobenzene	2	ND
Chloroethane	5	ND
Chloroform	5	ND
Chloromethane	10	ND
2&4-Chlorotoluene	2	ND
Dibromochloromethane	2	ND
1,2-Dibromo-3-Chloropropane	2	ND
1,2-Dibromoethane	2	ND
Dibromomethane	2	ND




ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REF.#: 92,071

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
1,2-Dichlorobenzene	2	ND
1,3-Dichlorobenzene	2	ND
1,4-Dichlorobenzene	2	ND
Dichlorodifluoromethane	10	ND
1,1-Dichloroethane	2	ND
1,2-Dichloroethane	2	ND
1,1-Dichloroethene	2	TBQ ²
cis-1,2-Dichloroethene	2	ND
trans-1,2-Dichloroethene	2	ND
1,2-Dichloropropane	2	ND
1,3-Dichloropropane	2	ND
2,2-Dichloropropane	2	ND
1,1-Dichloropropene	2	ND
cis-1,3-Dichloropropene	2	ND
trans-1,3-Dichloropropene	2	ND
Ethylbenzene	2	ND
Hexachlorobutadiene	5	ND
Isopropylbenzene	2	ND
p-Isopropyltoluene	2	ND
Methylene Chloride	10	ND
Naphthalene	10	ND
n-Propylbenzene	2	ND
Styrene	2	ND
1,1,1,2-Tetrachloroethane	2	ND
1,1,2,2-Tetrachloroethane	2	ND
Tetrachloroethene	2	ND



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REF.#: 92,071

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Toluene	2	ND
1,2,3-Trichlorobenzene	2	ND
1,2,4-Trichlorobenzene	2	ND
1,1,1-Trichloroethane	2	30.7
1,1,2-Trichloroethane	2	ND
Trichloroethene	2	ND
Trichlorofluoromethane	2	ND
1,2,3-Trichloropropane	2	ND
1,2,4-Trimethylbenzene	2	ND
1,3,5-Trimethylbenzene	2	ND
Vinyl Chloride	10	ND
Total Xylenes	2	ND
MTBE	5	ND

NUMBER OF UNIDENTIFIED PEAKS FOUND: 0

ANALYTICAL SURROGATE RECOVERY:

Dibromofluoromethane : 104.%

Toluene-d8 : 112.%

4-Bromofluorobenzene : 113.%

NOTES:

1 None detected

2 Trace below quantitation limit



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

LABORATORY REPORT

EPA METHOD 8260 WATER MATRIX

CLIENT: Nelson, Heindel, and Noyes, Inc.
PROJECT NAME: AOT/Brattleboro Garage
REPORT DATE: August 6, 1996
DATE SAMPLED: August 1, 1996
DATE RECEIVED: August 2, 1996
ANALYSIS DATE: August 5, 1996

PROJECT CODE: HNAO1621
REF.#: 92,072
STATION: MW-11
TIME SAMPLED: 4:15
SAMPLER: K.A.D./J.W.

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Benzene	2	ND ¹
Bromobenzene	2	ND
Bromochloromethane	2	ND
Bromodichloromethane	2	ND
Bromoform	2	ND
Bromomethane	5	ND
n-Butylbenzene	2	ND
sec-Butylbenzene	2	ND
Carbon Tetrachloride	2	ND
Chlorobenzene	2	ND
Chloroethane	5	ND
Chloroform	5	ND
Chloromethane	10	ND
2&4-Chlorotoluene	2	ND
Dibromochloromethane	2	ND
1,2-Dibromo-3-Chloropropane	2	ND
1,2-Dibromoethane	2	ND
Dibromomethane	2	ND



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REF.#: 92,072

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
1,2-Dichlorobenzene	2	ND
1,3-Dichlorobenzene	2	ND
1,4-Dichlorobenzene	2	ND
Dichlorodifluoromethane	10	ND
1,1-Dichloroethane	2	ND
1,2-Dichloroethane	2	ND
1,1-Dichloroethene	2	TBQ ²
cis-1,2-Dichloroethene	2	ND
trans-1,2-Dichloroethene	2	ND
1,2-Dichloropropane	2	ND
1,3-Dichloropropane	2	ND
2,2-Dichloropropane	2	ND
1,1-Dichloropropene	2	ND
cis-1,3-Dichloropropene	2	ND
trans-1,3-Dichloropropene	2	ND
Ethylbenzene	2	ND
Hexachlorobutadiene	5	ND
Isopropylbenzene	2	ND
p-Isopropyltoluene	2	ND
Methylene Chloride	10	ND
Naphthalene	10	ND
n-Propylbenzene	2	ND
Styrene	2	ND
1,1,1,2-Tetrachloroethane	2	ND
1,1,2,2-Tetrachloroethane	2	ND
Tetrachloroethene	2	8.3



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REF.#: 92,072

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Toluene	2	ND
1,2,3-Trichlorobenzene	2	ND
1,2,4-Trichlorobenzene	2	ND
1,1,1-Trichloroethane	2	8.5
1,1,2-Trichloroethane	2	ND
Trichloroethene	2	ND
Trichlorofluoromethane	2	ND
1,2,3-Trichloropropane	2	ND
1,2,4-Trimethylbenzene	2	ND
1,3,5-Trimethylbenzene	2	ND
Vinyl Chloride	10	ND
Total Xylenes	2	ND
MTBE	5	ND

NUMBER OF UNIDENTIFIED PEAKS FOUND: 0

ANALYTICAL SURROGATE RECOVERY:

Dibromofluoromethane : 101.%

Toluene-d8 : 99.%

4-Bromofluorobenzene : 114.%

NOTES:

1 None detected

2 Trace below quantitation limit



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

LABORATORY REPORT

EPA METHOD 8260 WATER MATRIX

CLIENT: Nelson, Heindel, and Noyes, Inc.
PROJECT NAME: AOT/Brattleboro Garage
REPORT DATE: August 6, 1996
DATE SAMPLED: August 1, 1996
DATE RECEIVED: August 2, 1996
ANALYSIS DATE: August 5, 1996

PROJECT CODE: HNAO1621
REF.#: 92,073
STATION: MW-15
TIME SAMPLED: 3:20
SAMPLER: K.A.D./J.W.

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Benzene	2	ND ¹
Bromobenzene	2	ND
Bromochloromethane	2	ND
Bromodichloromethane	2	ND
Bromoform	2	ND
Bromomethane	5	ND
n-Butylbenzene	2	ND
sec-Butylbenzene	2	ND
Carbon Tetrachloride	2	ND
Chlorobenzene	2	ND
Chloroethane	5	ND
Chloroform	5	ND
Chloromethane	10	ND
2&4-Chlorotoluene	2	ND
Dibromochloromethane	2	ND
1,2-Dibromo-3-Chloropropane	2	ND
1,2-Dibromoethane	2	ND
Dibromomethane	2	ND



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REF.#: 92,073

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
1,2-Dichlorobenzene	2	ND
1,3-Dichlorobenzene	2	ND
1,4-Dichlorobenzene	2	ND
Dichlorodifluoromethane	10	ND
1,1-Dichloroethane	2	ND
1,2-Dichloroethane	2	ND
1,1-Dichloroethene	2	ND
cis-1,2-Dichloroethene	2	ND
trans-1,2-Dichloroethene	2	ND
1,2-Dichloropropane	2	ND
1,3-Dichloropropane	2	ND
2,2-Dichloropropane	2	ND
1,1-Dichloropropene	2	ND
cis-1,3-Dichloropropene	2	ND
trans-1,3-Dichloropropene	2	ND
Ethylbenzene	2	ND
Hexachlorobutadiene	5	ND
Isopropylbenzene	2	ND
p-Isopropyltoluene	2	ND
Methylene Chloride	10	ND
Naphthalene	10	ND
n-Propylbenzene	2	ND
Styrene	2	ND
1,1,1,2-Tetrachloroethane	2	ND
1,1,2,2-Tetrachloroethane	2	ND
Tetrachloroethene	2	ND



REF.#: 92,073

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Toluene	2	ND
1,2,3-Trichlorobenzene	2	ND
1,2,4-Trichlorobenzene	2	ND
1,1,1-Trichloroethane	2	ND
1,1,2-Trichloroethane	2	ND
Trichloroethene	2	ND
Trichlorofluoromethane	2	ND
1,2,3-Trichloropropane	2	ND
1,2,4-Trimethylbenzene	2	ND
1,3,5-Trimethylbenzene	2	ND
Vinyl Chloride	10	ND
Total Xylenes	2	ND
MTBE	5	ND

NUMBER OF UNIDENTIFIED PEAKS FOUND: 0

ANALYTICAL SURROGATE RECOVERY:

Dibromofluoromethane : 104.%

Toluene-d8 : 97.%

4-Bromofluorobenzene : 112.%

NOTES:

1 None detected



Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103


LABORATORY REPORT

EPA METHOD 8260 WATER MATRIX

CLIENT: Nelson, Heindel, and Noyes, Inc.
PROJECT NAME: AOT/Brattleboro Garage
REPORT DATE: August 6, 1996
DATE SAMPLED: August 1, 1996
DATE RECEIVED: August 2, 1996
ANALYSIS DATE: August 6, 1996

PROJECT CODE: HNAO1621
REF.#: 92,074
STATION: MW-16
TIME SAMPLED: 3:40
SAMPLER: K.A.D./J.W.

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Benzene	2	ND ¹
Bromobenzene	2	ND
Bromochloromethane	2	ND
Bromodichloromethane	2	ND
Bromoform	2	ND
Bromomethane	5	ND
n-Butylbenzene	2	ND
sec-Butylbenzene	2	ND
Carbon Tetrachloride	2	ND
Chlorobenzene	2	ND
Chloroethane	5	ND
Chloroform	5	ND
Chloromethane	10	ND
2&4-Chlorotoluene	2	ND
Dibromochloromethane	2	ND
1,2-Dibromo-3-Chloropropane	2	ND
1,2-Dibromoethane	2	ND
Dibromomethane	2	ND




ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REF.#: 92,074

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
1,2-Dichlorobenzene	2	ND
1,3-Dichlorobenzene	2	ND
1,4-Dichlorobenzene	2	ND
Dichlorodifluoromethane	10	ND
1,1-Dichloroethane	2	ND
1,2-Dichloroethane	2	ND
1,1-Dichloroethene	2	2.1
cis-1,2-Dichloroethene	2	ND
trans-1,2-Dichloroethene	2	ND
1,2-Dichloropropane	2	ND
1,3-Dichloropropane	2	ND
2,2-Dichloropropane	2	ND
1,1-Dichloropropene	2	ND
cis-1,3-Dichloropropene	2	ND
trans-1,3-Dichloropropene	2	ND
Ethylbenzene	2	ND
Hexachlorobutadiene	5	ND
Isopropylbenzene	2	ND
p-Isopropyltoluene	2	ND
Methylene Chloride	10	ND
Naphthalene	10	ND
n-Propylbenzene	2	ND
Styrene	2	ND
1,1,1,2-Tetrachloroethane	2	ND
1,1,2,2-Tetrachloroethane	2	ND
Tetrachloroethene	2	11.7



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REF.#: 92,074

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Toluene	2	ND
1,2,3-Trichlorobenzene	2	ND
1,2,4-Trichlorobenzene	2	ND
1,1,1-Trichloroethane	2	26.6
1,1,2-Trichloroethane	2	ND
Trichloroethene	2	ND
Trichlorofluoromethane	2	ND
1,2,3-Trichloropropane	2	ND
1,2,4-Trimethylbenzene	2	ND
1,3,5-Trimethylbenzene	2	ND
Vinyl Chloride	10	ND
Total Xylenes	2	ND
MTBE	5	ND

NUMBER OF UNIDENTIFIED PEAKS FOUND: 0

ANALYTICAL SURROGATE RECOVERY:

Dibromofluoromethane : 103.%

Toluene-d8 : 102.%

4-Bromofluorobenzene : 113.%

NOTES:

1 None detected



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

LABORATORY REPORT

EPA METHOD 8260 WATER MATRIX

CLIENT: Nelson, Heindel, and Noyes, Inc.
PROJECT NAME: AOT/Brattleboro Garage
REPORT DATE: August 6, 1996
DATE SAMPLED: August 1, 1996
DATE RECEIVED: August 2, 1996
ANALYSIS DATE: August 6, 1996

PROJECT CODE: HNAO1621
REF.#: 92,075
STATION: MW-17
TIME SAMPLED: 2:50
SAMPLER: K.A.D./J.W.

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Benzene	2	ND ¹
Bromobenzene	2	ND
Bromochloromethane	2	ND
Bromodichloromethane	2	ND
Bromoform	2	ND
Bromomethane	5	ND
n-Butylbenzene	2	ND
sec-Butylbenzene	2	ND
Carbon Tetrachloride	2	ND
Chlorobenzene	2	ND
Chloroethane	5	ND
Chloroform	5	ND
Chloromethane	10	ND
2&4-Chlorotoluene	2	ND
Dibromochloromethane	2	ND
1,2-Dibromo-3-Chloropropane	2	ND
1,2-Dibromoethane	2	ND
Dibromomethane	2	ND



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REF.#: 92,075

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
1,2-Dichlorobenzene	2	ND
1,3-Dichlorobenzene	2	ND
1,4-Dichlorobenzene	2	ND
Dichlorodifluoromethane	10	ND
1,1-Dichloroethane	2	ND
1,2-Dichloroethane	2	ND
1,1-Dichloroethene	2	4.3
cis-1,2-Dichloroethene	2	ND
trans-1,2-Dichloroethene	2	ND
1,2-Dichloropropane	2	ND
1,3-Dichloropropane	2	ND
2,2-Dichloropropane	2	ND
1,1-Dichloropropene	2	ND
cis-1,3-Dichloropropene	2	ND
trans-1,3-Dichloropropene	2	ND
Ethylbenzene	2	ND
Hexachlorobutadiene	5	ND
Isopropylbenzene	2	ND
p-Isopropyltoluene	2	ND
Methylene Chloride	10	ND
Naphthalene	10	ND
n-Propylbenzene	2	ND
Styrene	2	ND
1,1,1,2-Tetrachloroethane	2	ND
1,1,2,2-Tetrachloroethane	2	ND
Tetrachloroethene	2	23.0



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REF.#: 92,075

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Toluene	2	ND
1,2,3-Trichlorobenzene	2	ND
1,2,4-Trichlorobenzene	2	ND
1,1,1-Trichloroethane	2	45.4
1,1,2-Trichloroethane	2	ND
Trichloroethene	2	ND
Trichlorofluoromethane	2	ND
1,2,3-Trichloropropane	2	ND
1,2,4-Trimethylbenzene	2	ND
1,3,5-Trimethylbenzene	2	ND
Vinyl Chloride	10	ND
Total Xylenes	2	ND
MTBE	5	ND

NUMBER OF UNIDENTIFIED PEAKS FOUND: 0

ANALYTICAL SURROGATE RECOVERY:


Dibromofluoromethane : 105.%

Toluene-d8 : 98.%

4-Bromofluorobenzene : 117.%

NOTES:

1 None detected



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

LABORATORY REPORT

EPA METHOD 8260 WATER MATRIX

CLIENT: Nelson, Heindel, and Noyes, Inc.
PROJECT NAME: AOT/Brattleboro Garage
REPORT DATE: August 6, 1996
DATE SAMPLED: August 1, 1996
DATE RECEIVED: August 2, 1996
ANALYSIS DATE: August 6, 1996

PROJECT CODE: HNAO1621
REF.#: 92,076
STATION: MW-18
TIME SAMPLED: 2:45
SAMPLER: K.A.D./J.W.

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Benzene	2	ND ¹
Bromobenzene	2	ND
Bromochloromethane	2	ND
Bromodichloromethane	2	ND
Bromoform	2	ND
Bromomethane	5	ND
n-Butylbenzene	2	ND
sec-Butylbenzene	2	ND
Carbon Tetrachloride	2	ND
Chlorobenzene	2	ND
Chloroethane	5	ND
Chloroform	5	ND
Chloromethane	10	ND
2&4-Chlorotoluene	2	ND
Dibromochloromethane	2	ND
1,2-Dibromo-3-Chloropropane	2	ND
1,2-Dibromoethane	2	ND
Dibromomethane	2	ND



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REF.#: 92,076

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
1,2-Dichlorobenzene	2	ND
1,3-Dichlorobenzene	2	ND
1,4-Dichlorobenzene	2	ND
Dichlorodifluoromethane	10	ND
1,1-Dichloroethane	2	ND
1,2-Dichloroethane	2	ND
1,1-Dichloroethene	2	ND
cis-1,2-Dichloroethene	2	ND
trans-1,2-Dichloroethene	2	ND
1,2-Dichloropropane	2	ND
1,3-Dichloropropane	2	ND
2,2-Dichloropropane	2	ND
1,1-Dichloropropene	2	ND
cis-1,3-Dichloropropene	2	ND
trans-1,3-Dichloropropene	2	ND
Ethylbenzene	2	ND
Hexachlorobutadiene	5	ND
Isopropylbenzene	2	ND
p-Isopropyltoluene	2	ND
Methylene Chloride	10	ND
Naphthalene	10	ND
n-Propylbenzene	2	ND
Styrene	2	ND
1,1,1,2-Tetrachloroethane	2	ND
1,1,2,2-Tetrachloroethane	2	ND
Tetrachloroethene	2	3.7



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REF.#: 92,076

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Toluene	2	ND
1,2,3-Trichlorobenzene	2	ND
1,2,4-Trichlorobenzene	2	ND
1,1,1-Trichloroethane	2	5.0
1,1,2-Trichloroethane	2	ND
Trichloroethene	2	ND
Trichlorofluoromethane	2	ND
1,2,3-Trichloropropane	2	ND
1,2,4-Trimethylbenzene	2	ND
1,3,5-Trimethylbenzene	2	ND
Vinyl Chloride	10	ND
Total Xylenes	2	ND
MTBE	5	ND

NUMBER OF UNIDENTIFIED PEAKS FOUND: 0

ANALYTICAL SURROGATE RECOVERY:

Dibromofluoromethane : 103.%

Toluene-d8 : 101.%

4-Bromofluorobenzene : 113.%

NOTES:

1 None detected



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

LABORATORY REPORT

EPA METHOD 8260 WATER MATRIX

CLIENT: Nelson, Heindel, and Noyes, Inc.
PROJECT NAME: AOT/Brattleboro Garage
REPORT DATE: August 6, 1996
DATE SAMPLED: August 1, 1996
DATE RECEIVED: August 2, 1996
ANALYSIS DATE: August 6, 1996

PROJECT CODE: HNAO1621
REF.#: 92,077
STATION: MW-19
TIME SAMPLED: 2:20
SAMPLER: K.A.D./J.W.

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Benzene	2	ND ¹
Bromobenzene	2	ND
Bromochloromethane	2	ND
Bromodichloromethane	2	ND
Bromoform	2	ND
Bromomethane	5	ND
n-Butylbenzene	2	ND
sec-Butylbenzene	2	ND
Carbon Tetrachloride	2	ND
Chlorobenzene	2	ND
Chloroethane	5	ND
Chloroform	5	TBQ ²
Chloromethane	10	ND
2&4-Chlorotoluene	2	ND
Dibromochloromethane	2	ND
1,2-Dibromo-3-Chloropropane	2	ND
1,2-Dibromoethane	2	ND
Dibromomethane	2	ND



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REF.#: 92,077

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
1,2-Dichlorobenzene	2	ND
1,3-Dichlorobenzene	2	ND
1,4-Dichlorobenzene	2	ND
Dichlorodifluoromethane	10	ND
1,1-Dichloroethane	2	ND
1,2-Dichloroethane	2	ND
1,1-Dichloroethene	2	TBQ
cis-1,2-Dichloroethene	2	ND
trans-1,2-Dichloroethene	2	ND
1,2-Dichloropropane	2	ND
1,3-Dichloropropane	2	ND
2,2-Dichloropropane	2	ND
1,1-Dichloropropene	2	ND
cis-1,3-Dichloropropene	2	ND
trans-1,3-Dichloropropene	2	ND
Ethylbenzene	2	ND
Hexachlorobutadiene	5	ND
Isopropylbenzene	2	ND
p-Isopropyltoluene	2	ND
Methylene Chloride	10	ND
Naphthalene	10	ND
n-Propylbenzene	2	ND
Styrene	2	ND
1,1,1,2-Tetrachloroethane	2	ND
1,1,2,2-Tetrachloroethane	2	ND
Tetrachloroethene	2	8.2



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REF.#: 92,077

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Toluene	2	ND
1,2,3-Trichlorobenzene	2	ND
1,2,4-Trichlorobenzene	2	ND
1,1,1-Trichloroethane	2	7.5
1,1,2-Trichloroethane	2	ND
Trichloroethene	2	ND
Trichlorofluoromethane	2	ND
1,2,3-Trichloropropane	2	ND
1,2,4-Trimethylbenzene	2	ND
1,3,5-Trimethylbenzene	2	ND
Vinyl Chloride	10	ND
Total Xylenes	2	ND
MTBE	5	ND

NUMBER OF UNIDENTIFIED PEAKS FOUND: 0

ANALYTICAL SURROGATE RECOVERY:

Dibromofluoromethane : 109.%


Toluene-d8 : 101.%

4-Bromofluorobenzene : 110.%

NOTES:

1 None detected

2 Trace below quantitation limit



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103


LABORATORY REPORT

EPA METHOD 8260 WATER MATRIX

CLIENT: Nelson, Heindel, and Noyes, Inc.
PROJECT NAME: AOT/Brattleboro Garage
REPORT DATE: August 6, 1996
DATE SAMPLED: August 1, 1996
DATE RECEIVED: August 2, 1996
ANALYSIS DATE: August 6, 1996


PROJECT CODE: HNAO1621
REF.#: 92,078
STATION: MW-20
TIME SAMPLED: 1:30
SAMPLER: K.A.D./J.W.

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Benzene	2	ND ¹
Bromobenzene	2	ND
Bromochloromethane	2	ND
Bromodichloromethane	2	ND
Bromoform	2	ND
Bromomethane	5	ND
n-Butylbenzene	2	ND
sec-Butylbenzene	2	ND
Carbon Tetrachloride	2	ND
Chlorobenzene	2	ND
Chloroethane	5	ND
Chloroform	5	ND
Chloromethane	10	ND
2&4-Chlorotoluene	2	ND
Dibromochloromethane	2	ND
1,2-Dibromo-3-Chloropropane	2	ND
1,2-Dibromoethane	2	ND
Dibromomethane	2	ND



REF.#: 92,078

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
1,2-Dichlorobenzene	2	ND
1,3-Dichlorobenzene	2	ND
1,4-Dichlorobenzene	2	ND
Dichlorodifluoromethane	10	ND
1,1-Dichloroethane	2	ND
1,2-Dichloroethane	2	ND
1,1-Dichloroethene	2	ND
cis-1,2-Dichloroethene	2	ND
trans-1,2-Dichloroethene	2	ND
1,2-Dichloropropane	2	ND
1,3-Dichloropropane	2	ND
2,2-Dichloropropane	2	ND
1,1-Dichloropropene	2	ND
cis-1,3-Dichloropropene	2	ND
trans-1,3-Dichloropropene	2	ND
Ethylbenzene	2	ND
Hexachlorobutadiene	5	ND
Isopropylbenzene	2	ND
p-Isopropyltoluene	2	ND
Methylene Chloride	10	ND
Naphthalene	10	ND
n-Propylbenzene	2	ND
Styrene	2	ND
1,1,1,2-Tetrachloroethane	2	ND
1,1,2,2-Tetrachloroethane	2	ND
Tetrachloroethene	2	ND



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REF.#: 92,078

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Toluene	2	ND
1,2,3-Trichlorobenzene	2	ND
1,2,4-Trichlorobenzene	2	ND
1,1,1-Trichloroethane	2	ND
1,1,2-Trichloroethane	2	ND
Trichloroethene	2	ND
Trichlorofluoromethane	2	ND
1,2,3-Trichloropropane	2	ND
1,2,4-Trimethylbenzene	2	ND
1,3,5-Trimethylbenzene	2	ND
Vinyl Chloride	10	ND
Total Xylenes	2	ND
MTBE	5	ND

NUMBER OF UNIDENTIFIED PEAKS FOUND: 0

ANALYTICAL SURROGATE RECOVERY:

Dibromofluoromethane : 108.%

Toluene-d8 : 99.%

4-Bromofluorobenzene : 116.%

NOTES:

1 None detected



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103


LABORATORY REPORT

EPA METHOD 8260 WATER MATRIX

CLIENT: Nelson, Heindel, and Noyes, Inc.
PROJECT NAME: AOT/Brattleboro Garage
REPORT DATE: August 6, 1996
DATE SAMPLED: August 1, 1996
DATE RECEIVED: August 2, 1996
ANALYSIS DATE: August 6, 1996

PROJECT CODE: HNAO1621
REF.#: 92,079
STATION: MW-21
TIME SAMPLED: 1:45
SAMPLER: K.A.D./J.W.

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Benzene	2	ND ¹
Bromobenzene	2	ND
Bromochloromethane	2	ND
Bromodichloromethane	2	ND
Bromoform	2	ND
Bromomethane	5	ND
n-Butylbenzene	2	ND
sec-Butylbenzene	2	ND
Carbon Tetrachloride	2	ND
Chlorobenzene	2	ND
Chloroethane	5	ND
Chloroform	5	ND
Chloromethane	10	ND
2&4-Chlorotoluene	2	ND
Dibromochloromethane	2	ND
1,2-Dibromo-3-Chloropropane	2	ND
1,2-Dibromoethane	2	ND
Dibromomethane	2	ND



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REF.#: 92,079

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
1,2-Dichlorobenzene	2	ND
1,3-Dichlorobenzene	2	ND
1,4-Dichlorobenzene	2	ND
Dichlorodifluoromethane	10	ND
1,1-Dichloroethane	2	ND
1,2-Dichloroethane	2	ND
1,1-Dichloroethene	2	ND
cis-1,2-Dichloroethene	2	ND
trans-1,2-Dichloroethene	2	ND
1,2-Dichloropropane	2	ND
1,3-Dichloropropane	2	ND
2,2-Dichloropropane	2	ND
1,1-Dichloropropene	2	ND
cis-1,3-Dichloropropene	2	ND
trans-1,3-Dichloropropene	2	ND
Ethylbenzene	2	ND
Hexachlorobutadiene	5	ND
Isopropylbenzene	2	ND
p-Isopropyltoluene	2	ND
Methylene Chloride	10	ND
Naphthalene	10	ND
n-Propylbenzene	2	ND
Styrene	2	ND
1,1,1,2-Tetrachloroethane	2	ND
1,1,1,2-Tetrachloroethane	2	ND
Tetrachloroethene	2	ND



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REF.#: 92,079

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Toluene	2	ND
1,2,3-Trichlorobenzene	2	ND
1,2,4-Trichlorobenzene	2	ND
1,1,1-Trichloroethane	2	ND
1,1,2-Trichloroethane	2	ND
Trichloroethene	2	ND
Trichlorofluoromethane	2	ND
1,2,3-Trichloropropane	2	ND
1,2,4-Trimethylbenzene	2	ND
1,3,5-Trimethylbenzene	2	ND
Vinyl Chloride	10	ND
Total Xylenes	2	ND
MTBE	5	ND

NUMBER OF UNIDENTIFIED PEAKS FOUND: 0

ANALYTICAL SURROGATE RECOVERY:

Dibromofluoromethane : 107.%

Toluene-d8 : 100.%

4-Bromofluorobenzene : 116.%

NOTES:

1 None detected



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

LABORATORY REPORT

EPA METHOD 8260 WATER MATRIX

CLIENT: Nelson, Heindel, and Noyes, Inc.
PROJECT NAME: AOT/Brattleboro Garage
REPORT DATE: August 6, 1996
DATE SAMPLED: August 1, 1996
DATE RECEIVED: August 2, 1996
ANALYSIS DATE: August 6, 1996

PROJECT CODE: HNAO1621
REF.#: 92,080
STATION: Trip Blank
TIME SAMPLED: 7:30
SAMPLER: K.A.D./J.W.

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Benzene	2	ND ¹
Bromobenzene	2	ND
Bromochloromethane	2	ND
Bromodichloromethane	2	ND
Bromoform	2	ND
Bromomethane	5	ND
n-Butylbenzene	2	ND
sec-Butylbenzene	2	ND
Carbon Tetrachloride	2	ND
Chlorobenzene	2	ND
Chloroethane	5	ND
Chloroform	5	ND
Chloromethane	10	ND
2&4-Chlorotoluene	2	ND
Dibromochloromethane	2	ND
1,2-Dibromo-3-Chloropropane	2	ND
1,2-Dibromoethane	2	ND
Dibromomethane	2	ND



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REF.#: 92,080

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
1,2-Dichlorobenzene	2	ND
1,3-Dichlorobenzene	2	ND
1,4-Dichlorobenzene	2	ND
Dichlorodifluoromethane	10	ND
1,1-Dichloroethane	2	ND
1,2-Dichloroethane	2	ND
1,1-Dichloroethene	2	ND
cis-1,2-Dichloroethene	2	ND
trans-1,2-Dichloroethene	2	ND
1,2-Dichloropropane	2	ND
1,3-Dichloropropane	2	ND
2,2-Dichloropropane	2	ND
1,1-Dichloropropene	2	ND
cis-1,3-Dichloropropene	2	ND
trans-1,3-Dichloropropene	2	ND
Ethylbenzene	2	ND
Hexachlorobutadiene	5	ND
Isopropylbenzene	2	ND
p-Isopropyltoluene	2	ND
Methylene Chloride	10	ND
Naphthalene	10	ND
n-Propylbenzene	2	ND
Styrene	2	ND
1,1,1,2-Tetrachloroethane	2	ND
1,1,2,2-Tetrachloroethane	2	ND
Tetrachloroethene	2	ND



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

REF.#: 92,080

<u>Parameter</u>	<u>Detection Limit (ug/L)</u>	<u>Concentration (ug/L)</u>
Toluene	2	ND
1,2,3-Trichlorobenzene	2	ND
1,2,4-Trichlorobenzene	2	ND
1,1,1-Trichloroethane	2	ND
1,1,2-Trichloroethane	2	ND
Trichloroethene	2	ND
Trichlorofluoromethane	2	ND
1,2,3-Trichloropropane	2	ND
1,2,4-Trimethylbenzene	2	ND
1,3,5-Trimethylbenzene	2	ND
Vinyl Chloride	10	ND
Total Xylenes	2	ND
MTBE	5	ND

NUMBER OF UNIDENTIFIED PEAKS FOUND: 0

ANALYTICAL SURROGATE RECOVERY:

Dibromofluoromethane : 102.%

Toluene-d8 : 99.%

4-Bromofluorobenzene : 117.%

NOTES:

1 None detected



ENDYNE, INC.

Laboratory Services

32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333
FAX 879-7103

EPA METHOD 8260 WATER MATRIX

MATRIX SPIKE AND DUPLICATE LABORATORY CONTROL DATA

CLIENT: Nelson, Heindel, and Noyes, Inc.
PROJECT NAME: AOT/Brattleboro Garage
REPORT DATE: August 6, 1996
DATE SAMPLED: August 1, 1996
DATE RECEIVED: August 2, 1996
ANALYSIS DATE: August 5, 1996

PROJECT CODE: HNAO1621
REF.#: 92,072
STATION: MW-11
TIME SAMPLED: 4:15
SAMPLER: K.A.D./J.W.

<u>Parameter</u>	<u>Sample</u> <u>(ug/L)</u>	<u>Spike</u> <u>(ug/L)</u>	<u>Dup 1</u> <u>(ug/L)</u>	<u>Dup 2</u> <u>(ug/L)</u>	<u>Average</u> <u>% Recovery</u>
1,1-Dichloroethene	TBQ ¹	50.0	46.5	45.9	92.%
Benzene	ND ²	50.0	52.3	51.5	104.%
Trichloroethene	ND	50.0	51.2	51.9	103.%
Toluene	ND	50.0	48.7	48.6	97.%
Chlorobenzene	ND	50.0	56.0	55.9	112.%

NOTES:

1 Trace below quantitation limit

2 None detected



32 James Brown Drive
Williston, Vermont 05495
(802) 879-4333

19755

CHAIN-OF-CUSTODY RECORD

Project Name: AOT/BRATTLEBORD GARAGE Site Location: LACROIX PROPERTY BRATTLEBORD, VT	Reporting Address: NHEN	Billing Address: NHEN
Endyne Project Number: HNA01621	Company: JEN Contact Name/Phone #: NHEN	Sampler Name: KAD/JW Phone #: NHEN 658-0820

[illegible]

Relinquished by: Signature <i>Kristin D. Pickett</i>	Received by: Signature <i>M. Chambers</i>	Date/Time <i>8/2/96 9:35 am</i>
Relinquished by: Signature	Received by: Signature	Date/Time

New York State Project: Yes _____ No _____

Requested Analyses

[illegible]